

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Samakhunta	Gram Panchayat	Sindurgoura

Work Code	OD/365/3506/120341/389118/00050362 (Development of Bongeji Rural Haat)
Project Category	Other Infrastructure

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Samakhunta	Proposal Date	-
Date of Commencement	30-12-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Development of Rural Haat
Project Sub-Category	Rural Haat	Project Type	Upgradation or Improvement
Name of Executant	SUSHANTA PANDUA		

Administrative Approval Details

Approval No.	OD/365/3506/120341/389118/00050362/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/365/3506/120341/389118/00050362/TS
Fund Sanction No.	31804
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Dismantling (AR1612) : Dismantling and removing 2.5 cm. thick artificial stone flooring - Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	1138.324748	Sqm
i	Un-Skilled	0.21505376344086	244.80102107527	-

2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	31.818652233126	Cum
i	Un-Skilled	0.1236	3.9327854160144	-
3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	13.2019717632	Cum
i	Skilled	0.18	2.376354917376	-
ii	Un-Skilled	3.9	51.48768987648	-

4	<p>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth</p> <p>- Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	9.495189376	Cum
i	Un-Skilled	2.96	28.10576055296	-
ii	Skilled	1.05	9.9699488448	-
iii	Highly-Skilled	0.35	3.3233162816	-
5	<p>Roofing (AR1132) : Supplying, feeting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties</p> <p>- Supplying, fitting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge</p>	-	329.14418064	Sqm
i	Un-Skilled	0.21505376344086	70.78369476129	-

	ii	Highly-Skilled	0.16129032258065	53.087771070968	-
6		Plastering (AR1004) : 12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	37.532812	Sqm
	i	Un-Skilled	0.12	4.50393744	-
	ii	Skilled	0.14	5.25459368	-
7		Flooring (AR0820) : 2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size hard broken(crusher broken) granite Chips - 2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size hard broken(crusher broken) granite Chips including curing for seven days with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	156.07704	Sqm
	i	Un-Skilled	0.36	56.1877344	-
	ii	Highly-Skilled	0.103	16.07593512	-

8	Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	75.065624	Sqm
i	Highly-Skilled	0.053763440860215	4.0357862365591	-
ii	Un-Skilled	0.053763440860215	4.0357862365591	-
9	Road Work (AR1307) : Supplying & spreading moorum and consolidation with HRR - Supplying & spreading moorum and consolidation with HRR including cost, conveyance, royalty, taxes cost of all labour & material, hire charges of T & P materials required for work as per specification and complete as per direction of Engineer-in-Charge.	-	142.394709984	Cum
i	Un-Skilled	1.0600706713781	150.94845581343	-

10	Earth Work (AR0122Bi) : Earthwork in ordinary soil within 5 Km. mechanical carriages and spreading in filling area/road berm within initial lead and lift - Earthwork in ordinary soil within 5 Km. mechanical carriages and spreading in filling area/road berm within initial lead and lift including dressing and leveling the bed, etc. as per direction of Engineer-in-Charge.	-	199.208688	Cum
i	Un-Skilled	0.32	63.74678016	-
11	Iron Work (AR1701) : Labour for hoisting joints, trusses and placing in position - Labour for hoisting joints, trusses and placing in position with all cost of labour and machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.	-	40	Qntl
i	Un-Skilled	0.33464566929134	13.385826771654	-
ii	Semi-Skilled	1.9685039370079	78.740157480315	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	691.91947250365	462	319666.79629669
1	Skilled	17.600897442176	562	9891.7043625029
2	Highly-Skilled	76.522808709127	612	46831.958929986
3	Semi-Skilled	78.740157480315	512	40314.960629921

