

ESTIMATION DPR							
State	Odisha	District	Kendujhar	Block	Patana	Gram Panchayat	Murusuan

Work Code	OD/361/3453/119486/385749/00051303 (Provision of Facility Centre at Murusuan GP Headquarters)
Project Category	Building

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Patana	Proposal Date	-
Date of Commencement	15-09-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant	KHELARAM MURMU		

Administrative Approval Details

Approval No.	OD/361/3453/119486/385749/00051303/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/361/3453/119486/385749/00051303/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	37.567684	Cum

	i	Un-Skilled	0.516	19.384924944	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	24.491555796378	Cum
	i	Un-Skilled	0.1236	3.0271562964323	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.205410955	Cum
	i	Skilled	0.18	1.4769739719	-
	ii	Un-Skilled	3.9	32.0011027245	-

4	Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	15.758864905	Cum
i	Un-Skilled	2.96	46.6462401188	-
ii	Skilled	1.05	16.54680815025	-
iii	Highly-Skilled	0.35	5.51560271675	-

5	Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	18.378380825	Cum
i	Un-Skilled	2.96	54.400007242	-
ii	Skilled	1.05	19.29729986625	-
iii	Highly-Skilled	0.35	6.43243328875	-

6	R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	2.703216	Cum
i	Un-Skilled	1.3333	3.6041978928	-
ii	Skilled	0.175	0.4730628	-
iii	Semi-Skilled	0.1323	0.3576354768	-

7	R.C.C. Work (AR0404Ab) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	2.2808218313	Cum
i	Un-Skilled	1.3333	3.0410197476723	-
ii	Skilled	0.35	0.798287640955	-
iii	Semi-Skilled	0.3073	0.70089654875849	-

8	R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	3.0640648852	Cum
i	Un-Skilled	1.3333	4.0853177114372	-
ii	Skilled	5.33875	16.358276405861	-
iii	Semi-Skilled	5.29605	16.227440835263	-

9	R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	1.211210285	Cum
i	Un-Skilled	1.3333	1.6149066729905	-
ii	Skilled	2.34375	2.8387741054688	-
iii	Semi-Skilled	2.30105	2.7870554262992	-

10	R.C.C. Work (AR0404Af) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Sun sheds & Chajja)	-	6.399881	Sqm
i	Un-Skilled	0.08333125	0.53331008358125	-
ii	Skilled	0.3423	2.1906792663	-
iii	Semi-Skilled	0.33963125	2.1735995838812	-

11	R.C.C. Work (AR0404Ag) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	6.5793255	Cum
i	Un-Skilled	1.3333	8.77221468915	-
ii	Skilled	3.15525	20.759416783875	-
iii	Semi-Skilled	3.11255	20.478479585025	-

12	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	16.3	Qntl
i	Un-Skilled	0.8	13.04	-
ii	Highly-Skilled	0.3	4.89	-
iii	Semi-Skilled	0.044	0.7172	-
13	<p>R.C.C. Work (AR0401) : R.C.C work - 'Reinforced cement concrete (1:2:4) work with 12mm size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (To be used for minor repair work only)</p>	-	0.4550562175	Cum
i	Un-Skilled	4.6	2.0932586005	-

	ii	Skilled	0.68	0.3094382279	-
14		Plastering (AR1017) : 20mm thick cement Plaster in CM (1:4) over masonry work in inside. - 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	43.686225	Sqm
	i	Un-Skilled	0.24	10.484694	-
	ii	Skilled	0.16	6.989796	-
15		Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	111.811653	Sqm
	i	Un-Skilled	0.24	26.83479672	-
	ii	Skilled	0.16	17.88986448	-

16	Plastering (AR1004) : 12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	96.27227	Sqm
i	Un-Skilled	0.12	11.5526724	-
ii	Skilled	0.14	13.4781178	-
17	Plastering (AR1006) : 12mm thick cement plaster (1:4) over brickwork in inside - 12mm thick cement plaster (1:4) over brickwork in inside with cement punning for skirting/wall punning including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc. comp. and as per direction of Engineer-in- charge.	-	19.03521	Sqm
i	Un-Skilled	0.11	2.0938731	-
ii	Skilled	0.15	2.8552815	-

18	<p>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	58.74603962	Sqm
i	Un-Skilled	0.17	9.9868267354	-
ii	Skilled	0.14	8.2244455468	-
19	<p>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	26.004568	Sqm
i	Un-Skilled	0.216	5.616986688	-
ii	Highly-Skilled	0.216	5.616986688	-

20	Flooring (AR0817aa) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.	-	3.142807	Sqm
i	Highly-Skilled	0.325	1.021412275	-
ii	Un-Skilled	0.325	1.021412275	-
iii	Semi-Skilled	0.76	2.38853332	-

21	<p>Flooring (AR0816) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in- charge.</p>	-	6.501142	Sqm
i	Un-Skilled	0.216	1.404246672	-
ii	Highly-Skilled	0.216	1.404246672	-
iii	Semi-Skilled	0.55	3.5756281	-

22	<p>Flooring (AR0817a) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in- charge</p>	-	27.9629	Sqm
i	Highly-Skilled	0.325	9.0879425	-
ii	Un-Skilled	0.325	9.0879425	-
iii	Semi-Skilled	0.76	21.251804	-

23	<p>Flooring (AR0816j) : Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 - Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	4.8308	Sqm
	i Un-Skilled	0.216	1.0434528	-
	ii Highly-Skilled	0.216	1.0434528	-
	iii Semi-Skilled	0.55	2.65694	-
24	<p>Other Building Items. (AR1902) : cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc. complete. and as per the direction of Engineer in Charge.</p>	-	170.56	Sqm
	i Un-Skilled	0.057	9.72192	-

	ii	Skilled	0.05	8.528	-
25		Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	170.56	Sqm
	i	Highly-Skilled	0.054	9.21024	-
	ii	Un-Skilled	0.064	10.91584	-
26		Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	170.56	Sqm
	i	Highly-Skilled	0.053763440860215	9.1698924731183	-
	ii	Un-Skilled	0.053763440860215	9.1698924731183	-

27	Painting (AR0918cb) : Finishing wall two coats with weather coat with one coat waterbound Primer - Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	96.27	Sqm
i	Un-Skilled	0.11776344086022	11.337086451613	-
ii	Highly-Skilled	0.10776344086022	10.374386451613	-
28	Painting (AR0903b) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	26.2907	Sqm
i	Highly-Skilled	0.18817204301075	4.9471747311828	-
ii	Un-Skilled	0.17204301075269	4.5231311827957	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	317.03843072179	462	146471.75499347
1	Skilled	139.01452254556	562	78126.161670605

2	Highly-Skilled	68.713770596414	612	42052.827605005
3	Semi-Skilled	73.315212876027	512	37537.388992526
				Total: 304188.1332616