

ESTIMATION DPR							
State	Odisha	District	Sonepur	Block	Tarbha	Gram Panchayat	Pua

Work Code	OD/372/3571/121500/419646/00051661 (Development of Rural Haat at Pua)
Project Category	Other Infrastructure

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Tarbha	Proposal Date	-
Date of Commencement	22-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Development of Rural Haat
Project Sub-Category	Rural Haat	Project Type	New Work
Name of Executant	KSHIRODINI NAIK		

Administrative Approval Details

Approval No.	OD/372/3571/121500/419646/00051661/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/372/3571/121500/419646/00051661/TS
Fund Sanction No.	20484
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	68.7816	Cum

	i	Un-Skilled	0.516	35.4913056	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	110.56542	Cum
	i	Un-Skilled	0.1236	13.665885912	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	27.611235	Cum
	i	Skilled	0.18	4.9700223	-
	ii	Un-Skilled	3.9	107.6838165	-

4	<p>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	60.8076	Cum
i	Un-Skilled	2.96	179.990496	-
ii	Skilled	1.05	63.84798	-
iii	Highly-Skilled	0.35	21.28266	-
5	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	20.226	Cum

	i	Un-Skilled	4.6	93.0396	-
	ii	Skilled	0.68	13.75368	-
6		Plastering (AR1004) : 12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	91.452	Sqm
	i	Un-Skilled	0.12	10.97424	-
	ii	Skilled	0.14	12.80328	-
7		Roofing (AR1132i) : Supplying, feeting & fixing of G.C.I. Sheet (0.40mm thick) in roof drilling hole in wind ties - Supplying, fitting & fixing of G.C.I. Sheet (0.40mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge	-	209.41	Sqm
	i	Un-Skilled	0.21505376344086	45.034408602151	-
	ii	Highly-Skilled	0.16129032258065	33.775806451613	-

8	miscellaneous (ARM106) : Labour for fitting and fixing of M.S. Gates as per approved design including cost of all materials complete (Iron works) and as directed by Engineer-in-Charge. - Labour for fitting and fixing of M.S. Gates as per approved design including cost of all materials complete (Iron works) and as directed by Engineer-in-Charge.	-	1863.7656	Sqm
---	---	---	-----------	-----

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	485.87975261415	462	224476.44570774
1	Skilled	95.3749623	562	53600.7288126
2	Highly-Skilled	55.058466451613	612	33695.781468387
Total:				311772.95598872