

ESTIMATION DPR							
State	Odisha	District	Sonepur	Block	Dunguripali	Gram Panchayat	Bankipali

Work Code	OD/372/3569/121455/419001/00051865 (MAINTANANCE OF CC ROAD FROM KANDAGAD HARIJANPADA TO PANKEL)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Dunguripali	Proposal Date	-
Date of Commencement	02-02-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES
Project Sub-Category	CC Road	Project Type	Upgradation or Improvement
Name of Executant	JAGYANSENI SAHU		

Administrative Approval Details

Approval No.	OD/372/3569/121455/419001/00051865/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/372/3569/121455/419001/00051865/TS
Fund Sanction No.	32004
Fund Sanction Amount (in Rs.)	500000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Meaurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	5.508	Cum

	i	Un-Skilled	0.516	2.842128	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	31.671	Cum
	i	Un-Skilled	0.1236	3.9145356	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	39.015	Cum
	i	Skilled	0.18	7.0227	-
	ii	Un-Skilled	3.9	152.1585	-

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	33.507	Cum
i	Un-Skilled	4.6	154.1322	-
ii	Skilled	0.68	22.78476	-
5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	91.8	Sqm
i	Semi-Skilled	0.05	4.59	-
ii	Skilled	0.05	4.59	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
--------	-------------	----------	------	--------

0	Un-Skilled	313.0473636	462	144627.8819832
1	Skilled	34.39746	562	19331.37252
2	Semi-Skilled	4.59	512	2350.08
				Total: 166309.3345032