

ESTIMATION DPR							
State	Odisha	District	Sundargarh	Block	Balisankara	Gram Panchayat	Bandega

Work Code	OD/373/3573/121522/383986/00051895 (CONSTRUCTION OF CC ROAD AT MURKIA NADIDHIPA SAY PADA)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Balisankara	Proposal Date	-
Date of Commencement	20-09-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	Seema Kirti Behera		

Administrative Approval Details

Approval No.	OD/373/3573/121522/383986/00051895/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/373/3573/121522/383986/00051895/TS
Fund Sanction No.	1130
Fund Sanction Amount (in Rs.)	186532

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0110) : Fine dressing of earth work in ordinary or hard soil in road formation - Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.	-	118.95	Sqm
i	Un-Skilled	0.01	1.1895	-

2	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	0.8	Cum
i	Un-Skilled	0.516	0.4128	-
3	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	5.9475	Cum
i	Un-Skilled	0.1236	0.735111	-

4	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	13.455	Cum
i	Skilled	0.18	2.4219	-
ii	Un-Skilled	3.9	52.4745	-
5	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	10.7055	Cum
i	Un-Skilled	4.6	49.2453	-
ii	Skilled	0.68	7.27974	-

6	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	22.62	Sqm
i	Semi-Skilled	0.05	1.131	-
ii	Skilled	0.05	1.131	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	104.057211	462	48074.431482
1	Skilled	10.83264	562	6087.94368
2	Semi-Skilled	1.131	512	579.072
Total:				54741.447162