

ESTIMATION DPR							
State	Odisha	District	Angul	Block	Chhendipada	Gram Panchayat	Barasahi

Work Code	OD/344/3279/115635/404441/00055225 (CONSTRUCTION OF CC ROAD FROM GAUDANALI SAHI TO MAJHI TUBE WELL)
Project Category	Road

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Chhendipada	Proposal Date	-
Date of Commencement	04-10-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	RAJESH KUMAR SAHU		

Administrative Approval Details

Approval No.	OD/344/3279/115635/404441/00055225/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/344/3279/115635/404441/00055225/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	201919

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	2.7310420928	Cum
i	Un-Skilled	0.516	1.4092177198848	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	0.5264659456	Cum
i	Un-Skilled	0.1236	0.06507119087616	-

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	2.1716720256	Cum
	i Skilled	0.18	0.390900964608	-
	ii Un-Skilled	3.9	8.46952089984	-
4	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	48.30956	Sqm
	i Semi-Skilled	0.05	2.415478	-
	ii Skilled	0.05	2.415478	-

5	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	21.733144	Cum
i	Un-Skilled	4.6	99.9724624	-
ii	Skilled	0.68	14.77853792	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	109.9162722106	462	50781.317761298
1	Skilled	17.584916884608	562	9882.7232891497
2	Semi-Skilled	2.415478	512	1236.724736
Total: 61900.765786447				