

ESTIMATION DPR

State	Odisha	District	Nabarangpur	Block	Jhorigam	Gram Panchayat	Dhodra
--------------	--------	-----------------	-------------	--------------	----------	-----------------------	--------

Work Code	OD/366/3515/120452/427406/00056402 (Construction work of VSS building at Niripadar village of Dhodra GP)
Project Category	Building

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Jhorigam	Proposal Date	22-07-2024
Date of Commencement	-	Date of Completion	-
Scheme Name	Construction of Vana Suraksha Samiti Building	Scheme Component Name	Construction of Buildings for Vana Suraksha Samiti
Project Sub-Category	Vana Suraksha Samiti Building	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	OD/366/3515/120452/427406/00056402/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/366/3515/120452/427406/00056402/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	850000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0122Aia) : Earthwork in all kinds of soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift - Earthwork in all kinds of soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge	-	28.2582	Cum

	i	Un-Skilled	0.5682408	16.05746217456	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	24.1593	Cum
	i	Un-Skilled	0.1236	2.98608948	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	18.20245	Cum
	i	Skilled	0.18	3.276441	-
	ii	Un-Skilled	3.9	70.989555	-

4	R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	17.69495945	Cum
i	Un-Skilled	1.3333	23.592689434685	-
ii	Skilled	0.1	1.769495945	-
iii	Semi-Skilled	0.0573	1.013921176485	-

5	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	19.1	Qntl
i	Un-Skilled	0.8	15.28	-
ii	Highly-Skilled	0.3	5.73	-
iii	Semi-Skilled	0.044	0.8404	-
6	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	108.2614	Sqm
i	Semi-Skilled	0.05	5.41307	-

	ii	Skilled	0.05	5.41307	-
7		R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	9.822	Sqm
	i	Semi-Skilled	0.16025641025641	1.5740384615385	-
	ii	Skilled	0.16025641025641	1.5740384615385	-
8		R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	13.096	Sqm
	i	Semi-Skilled	0.6547619047619	8.5747619047619	-
	ii	Skilled	0.6547619047619	8.5747619047619	-

9	R.C.C. Work (AR0410b) : centering and shuttering fRigid and smooth or R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. stairs excluding landing but including railing details for 5 Sqm	-	6.39	Sqm
i	Semi-Skilled	0.55	3.5145	-
ii	Skilled	0.55	3.5145	-
10	R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	47.768	Sqm
i	Semi-Skilled	0.305555555555556	14.5957777777778	-
ii	Skilled	0.305555555555556	14.5957777777778	-

11	<p>Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	22.046029	Cum
i	Un-Skilled	2.96	65.25624584	-
ii	Skilled	1.05	23.14833045	-
iii	Highly-Skilled	0.35	7.71611015	-
12	<p>Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.</p>	-	3.06	Qntl
i	Un-Skilled	6.3976377952756	19.576771653543	-

	ii	Semi-Skilled	1.9685039370079	6.0236220472441	-
	iii	Skilled	3.9370078740157	12.047244094488	-
	iv	Highly-Skilled	3.4448818897638	10.541338582677	-
13		<p>Other Building Items. (AR1909) : Al. door with OEL anodized Al. door section of 9202 as vertical member - Providing fitting, fixing of Al. door with OEL anodized Al. door section of 9202 as vertical member, 9201 as top member and 9200 as bottom and middle member and 12mm thick pre-laminated board fixed on door frame by means of tapered clip No. 4660 and the frame to be completed by means of jointing angle No.1855 including all cost of labour,T&P , hire charges of drilling machine, labour charges etc. complete. and as per direction of Engineer in Charge</p>	-	1.785	Sqm
	i	Un-Skilled	1.3888888888889	2.4791666666667	-
	ii	Semi-Skilled	1.0648148148148	1.9006944444444	-
	iii	Skilled	0.7777777777778	1.3883333333333	-
	iv	Highly-Skilled	0.1944444444444	0.3470833333333	-
	v		0.46296296296296	0.8263888888889	-

14	Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	132.252	Sqm
i	Un-Skilled	0.24	31.74048	-
ii	Skilled	0.16	21.16032	-
15	Plastering (AR1004) : 12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	83.17	Sqm
i	Un-Skilled	0.12	9.9804	-
ii	Skilled	0.14	11.6438	-

16	<p>Painting (AR0922a) : Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work (Inside) - Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	164.832	Sqm	
	i	Highly-Skilled	0.10576344086022	17.433199483871	-
	ii	Un-Skilled	0.11576344086022	19.081519483871	-
17	<p>Painting (AR0918h) : Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work(Outside). - Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)</p>	-	83.18	Sqm	
	i	Un-Skilled	0.11776344086022	9.7955630107527	-

	ii	Highly-Skilled	0.10776344086022	8.9637630107527	-
18		Painting (AR0903b) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	23.229	Sqm
	i	Highly-Skilled	0.18817204301075	4.3710483870968	-
	ii	Un-Skilled	0.17204301075269	3.9963870967742	-

19	<p>Flooring (AR0816) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in- charge.</p>	-	37.305	Sqm
i	Un-Skilled	0.216	8.05788	-
ii	Highly-Skilled	0.216	8.05788	-
iii	Semi-Skilled	0.55	20.51775	-

20	<p>Flooring (AR0817a) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in- charge</p>	-	9.2625	Sqm	
	i	Highly-Skilled	0.325	3.0103125	-
	ii	Un-Skilled	0.325	3.0103125	-
	iii	Semi-Skilled	0.76	7.0395	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	301.88052234085	462	139468.80132147
1	Skilled	108.1061129669	562	60755.635487398
2	Semi-Skilled	71.008035812252	512	36356.114335873
3	Highly-Skilled	66.170735447731	612	40496.490094011

4		0.82638888888889	50	41.319444444444
				Total: 277118.3606832