

ESTIMATION DPR							
State	Odisha	District	Rayagada	Block	Kasipur	Gram Panchayat	Bankamba

Work Code	OD/370/3552/121174/426105/00060524 (Maintenance and improvement of Roads at Dakli)
Project Category	Road

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Kasipur	Proposal Date	08-06-2021
Date of Commencement	31-10-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	KRISHNA PRIYA MANDAL		

Administrative Approval Details

Approval No.	OD/370/3552/121174/426105/00060524/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/370/3552/121174/426105/00060524/TS
Fund Sanction No.	9114
Fund Sanction Amount (in Rs.)	159826

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.98905	Cum
i	Un-Skilled	0.1236	2.09984658	-

2	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	14.68805	Cum
i	Skilled	0.18	2.643849	-
ii	Un-Skilled	3.9	57.283395	-
3	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	6.998875	Cum
i	Un-Skilled	4.6	32.194825	-
ii	Skilled	0.68	4.759235	-

4	Earth Work (AR0122Ai) : Earth work in all kinds of soil within 50m, initial lead and 1.5m, initial lift - Earth work in all kinds of soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	22.837425	Cum
i	Un-Skilled	0.473534	10.81429720995	-
5	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	7.67	Sqm
i	Semi-Skilled	0.05	0.3835	-
ii	Skilled	0.05	0.3835	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	102.39236378995	462	47305.272070957
1	Skilled	7.786584	562	4376.060208

2	Semi-Skilled	0.3835	512	196.352
				Total: 51877.684278957