

ESTIMATION DPR							
State	Odisha	District	Gajapati	Block	Rayagad	Gram Panchayat	Dambala

Work Code	OD/353/3363/117548/414752/00061008 (Improvement of Tank at Mandalsahi near Ashram School)						
Project Category	Water Body						

Financial Year	2020-21	Execution Level	PS
Executing Agency	Panchayat Samiti, Rayagad	Proposal Date	-
Date of Commencement	24-10-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Tank	Project Type	Upgradation or Improvement
Name of Executant	Janemejay Mohanta		

Administrative Approval Details

Approval No.	OD/353/3363/117548/414752/00061008/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/353/3363/117548/414752/00061008/TS
Fund Sanction No.	3971
Fund Sanction Amount (in Rs.)	300000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Earth Work (AR0103aa) : Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume in foundation and plinth within 50m. Initial lead and 1.5m - Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume in foundation and plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.3m in depth and as per specification approved by the department</p>	-	14.58	Cum
i	Un-Skilled	0.80472	11.7328176	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	5.55	Cum
i	Un-Skilled	0.1236	0.68598	-

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	34.3	Cum
i	Skilled	0.18	6.174	-
ii	Un-Skilled	3.9	133.77	-
4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	1.835	Cum
i	Un-Skilled	4.6	8.441	-
ii	Skilled	0.68	1.2478	-

5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	124.75	Sqm
i	Semi-Skilled	0.05	6.2375	-
ii	Skilled	0.05	6.2375	-
6	<p>Plastering (AR1008) : 20mm thick cement Plaster in CM (1:6) over brick work in inside. - 20mm thick cement Plaster in CM (1:6) for stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	22.05	Sqm
i	Un-Skilled	0.24	5.292	-
ii	Skilled	0.16	3.528	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
--------	-------------	----------	------	--------

0	Un-Skilled	159.9217976	462	73883.8704912
1	Skilled	17.1873	562	9659.2626
2	Semi-Skilled	6.2375	512	3193.6
				Total: 86736.7330912