

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Badasahi	Gram Panchayat	Khanua

Work Code	OD/365/3487/120050/390612/00061596 (CONSTRUCTION OF CC ROAD FROM DURGA CHARAN SINGH HOUSE TO MAHADEV SING HOUSE AT MUCHASAHU)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Badasahi	Proposal Date	14-02-2025
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	6908
Fund Sanction Amount (in Rs.)	186532

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	2.64	Cum

	i	Un-Skilled	0.516	1.36224	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	10.56	Cum
	i	Un-Skilled	0.1236	1.305216	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	12.54	Cum
	i	Skilled	0.18	2.2572	-
	ii	Un-Skilled	3.9	48.906	-

4	<p>R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</p>	-	13.2	Sqm
i	Semi-Skilled	0.305555555555556	4.03333333333333	-
ii	Skilled	0.305555555555556	4.03333333333333	-
5	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	11.88	Cum
i	Un-Skilled	4.6	54.648	-
ii	Skilled	0.68	8.0784	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	106.221456	462	49074.312672
1	Skilled	14.3689333333333	562	8075.34053333333
2	Semi-Skilled	4.03333333333333	512	2065.06666666667
				Total: 59214.719872