

ESTIMATION DPR							
State	Odisha	District	Cuttack	Block	Tigiria	Gram Panchayat	Baliput

Work Code	OD/350/3345/275453/398991/00062054 (REpair and Maint of Road from Rabi Dehuri House to Bilash Naik House , Godarabandha)
Project Category	Road

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Tigiria	Proposal Date	12-11-2021
Date of Commencement	06-12-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES
Project Sub-Category	CC Road	Project Type	Repair and Maintenance
Name of Executant	DIPTIMAYEE SAHU		

Administrative Approval Details

Approval No.	OD/350/3345/275453/398991/00062054/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/350/3345/275453/398991/00062054/TS
Fund Sanction No.	300000
Fund Sanction Amount (in Rs.)	300000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	7.090848	Cum

	i	Un-Skilled	0.516	3.658877568	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	15.63846114	Cum
	i	Un-Skilled	0.1236	1.932913796904	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	24.83651582	Cum
	i	Skilled	0.18	4.4705728476	-
	ii	Un-Skilled	3.9	96.862411698	-

4	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	46.554048	Sqm
i	Semi-Skilled	0.05	2.3277024	-
ii	Skilled	0.05	2.3277024	-
5	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.</p>	-	17.44102398	Cum
i	Un-Skilled	4.6	80.228710308	-
ii	Skilled	0.68	11.8598963064	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
--------	-------------	----------	------	--------

0	Un-Skilled	182.6829133709	462	84399.505977358
1	Skilled	18.658171554	562	10485.892413348
2	Semi-Skilled	2.3277024	512	1191.7836288
				Total: 96077.182019506