

ESTIMATION DPR

State	Odisha	District	Jajpur	Block	Dharmasala	Gram Panchayat	Abhayapur
--------------	--------	-----------------	--------	--------------	------------	-----------------------	-----------

Work Code	OD/356/3397/118327/401250/00063481 (CONSTRUCTION OF PAVER ROAD FROM KHETRABASI SAHOO HOUSE TO RAJENDRA BEHERA HOUSE)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Dharmasala	Proposal Date	-
Date of Commencement	05-11-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	Pavor Block	Project Type	New Work
Name of Executant	PRITIMAYEE SAMAL		

Administrative Approval Details

Approval No.	OD/356/3397/118327/401250/00063481/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/356/3397/118327/401250/00063481/TS
Fund Sanction No.	10574
Fund Sanction Amount (in Rs.)	500000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	11.12	Cum
i	Un-Skilled	0.516	5.73792	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</p> <p>Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	68.4575	Cum
i	Un-Skilled	0.1236	8.461347	-

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	22.24	Cum
i	Skilled	0.18	4.0032	-
ii	Un-Skilled	3.9	86.736	-
4	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	150.12	Sqm
i	Semi-Skilled	0.05	7.506	-
ii	Skilled	0.05	7.506	-

5	<p>miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	437.85	Sqm
---	--	---	--------	-----

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	100.935267	462	46632.093354
1	Skilled	11.5092	562	6468.1704
2	Semi-Skilled	7.506	512	3843.072
Total: 56943.335754				