

ESTIMATION DPR							
State	Odisha	District	Bhadrak	Block	Bhandaripokhari	Gram Panchayat	Tealnga

Work Code	OD/348/3324/116662/394513/00064553 (MAINTENANCE & IMPROVEMENT OF ROAD FROM CONNECTING MAIN ROAD TO IN FRONT OF SHIVA TEMPLE)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Bhandaripokhari	Proposal Date	-
Date of Commencement	20-11-2025	Date of Completion	07-12-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	Repair and Maintenance
Name of Executant	Adhyatmika Das		

Administrative Approval Details

Approval No.	OD/348/3324/116662/394513/00064553/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/348/3324/116662/394513/00064553/TS
Fund Sanction No.	11939
Fund Sanction Amount (in Rs.)	200000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	2.3	Cum
i	Un-Skilled	0.516	1.1868	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</p> <p>Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	25.47122	Cum
i	Un-Skilled	0.1236	3.148242792	-

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	2.64	Cum
i	Skilled	0.18	0.4752	-
ii	Un-Skilled	3.9	10.296	-
4	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	15	Sqm
i	Semi-Skilled	0.05	0.75	-
ii	Skilled	0.05	0.75	-

5	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	0.915	Cum
i	Un-Skilled	4.6	4.209	-
ii	Skilled	0.68	0.6222	-
6	<p>miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	240.8122	Sqm

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	18.840042792	462	8704.099769904
1	Skilled	1.8474	562	1038.2388
2	Semi-Skilled	0.75	512	384
				Total: 10126.338569904