

ESTIMATION DPR

State	Odisha	District	Balasore	Block	Simulia	Gram Panchayat	Abjhuna
--------------	--------	-----------------	----------	--------------	---------	-----------------------	---------

Work Code	OD/346/3308/116294/394259/00064943 (Road from Banamali Behera Ghar to pagoda rasta, Abjhuna UNTIED ,5th SFC)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Simulia	Proposal Date	-
Date of Commencement	01-01-2026	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	AJAYA MAJHI		

Administrative Approval Details

Approval No.	OD/346/3308/116294/394259/00064943/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/346/3308/116294/394259/00064943/TS
Fund Sanction No.	28365
Fund Sanction Amount (in Rs.)	102038

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	1.6302	Cum

	i	Un-Skilled	0.516	0.8411832	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	4.9894	Cum
	i	Un-Skilled	0.1236	0.61668984	-
3		Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	7.48904	Cum
	i	Un-Skilled	3.9	29.207256	-
	ii	Skilled	0.18	1.3480272	-

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	5.243316	Cum
i	Un-Skilled	4.6	24.1192536	-
ii	Skilled	0.68	3.56545488	-
5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	22.0818	Sqm
i	Semi-Skilled	0.05	1.10409	-
ii	Skilled	0.05	1.10409	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
--------	-------------	----------	------	--------

0	Un-Skilled	54.78438264	462	25310.38477968
1	Skilled	6.01757208	562	3381.87550896
2	Semi-Skilled	1.10409	512	565.29408
				Total: 29257.55436864