

ESTIMATION DPR							
State	Odisha	District	Nabarangpur	Block	Dabugam	Gram Panchayat	Dabugam

Work Code	OD/366/3514/120436/427679/00065086 (Repair and Renovation of Alekha Tungi at village Umurahandi)
Project Category	Religious Structures

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Dabugam	Proposal Date	-
Date of Commencement	28-11-2025	Date of Completion	15-01-2026
Scheme Name	Chief Minister Special Assistant	Scheme Component Name	Chief Minister Special Assistance (CM-SA)
Project Sub-Category	Religious Structures	Project Type	Renovation or Rejuvenation
Name of Executant	Abinash Nayak		

Administrative Approval Details

Approval No.	OD/366/3514/120436/427679/00065086/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/366/3514/120436/427679/00065086/TS
Fund Sanction No.	1276
Fund Sanction Amount (in Rs.)	250000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	11.550525	Cum

	i	Un-Skilled	0.516	5.9600709	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	20.564649	Cum
	i	Un-Skilled	0.1236	2.5417906164	-
3		Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.972739	Cum
	i	Un-Skilled	3.9	38.8936821	-
	ii	Skilled	0.18	1.79509302	-

4	R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	6.72748	Cum
i	Un-Skilled	1.3333	8.969749084	-
ii	Skilled	0.1	0.672748	-
iii	Semi-Skilled	0.0573	0.385484604	-

5	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	2.499372	Qntl
i	Un-Skilled	0.8	1.9994976	-
ii	Highly-Skilled	0.3	0.7498116	-
iii	Semi-Skilled	0.044	0.109972368	-
6	<p>Masonry Brick Work (AR0603) : K.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with K.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	6.930315	Cum

	i	Un-Skilled	2.96	20.5137324	-
	ii	Skilled	1.05	7.27683075	-
	iii	Highly-Skilled	0.35	2.42561025	-
7		Masonry Brick Work (AR0603i) : K.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with K.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	14.148756	Cum
	i	Un-Skilled	2.96	41.88031776	-
	ii	Skilled	1.05	14.8561938	-
	iii	Highly-Skilled	0.35	4.9520646	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	120.7588404604	462	55790.584292705
1	Skilled	24.60086557	562	13825.68645034

2	Semi-Skilled	0.495456972	512	253.673969664
3	Highly-Skilled	8.12748645	612	4974.0217074
				Total: 74843.966420109