

## ESTIMATION DPR

<b>State</b>	Odisha	<b>District</b>	Ganjam	<b>Block</b>	Polosara	<b>Gram Panchayat</b>	Balichai
--------------	--------	-----------------	--------	--------------	----------	-----------------------	----------

<b>Work Code</b>	OD/354/3380/117898/411379/00068310 (Completion of AWC-I at Nodal School Premises at Balichai)
<b>Project Category</b>	Building

<b>Financial Year</b>	2021-22	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Polosara	<b>Proposal Date</b>	18-06-2021
<b>Date of Commencement</b>	15-12-2025	<b>Date of Completion</b>	17-12-2025
<b>Scheme Name</b>	SFC Devolution of Fund	<b>Scheme Component Name</b>	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
<b>Project Sub-Category</b>	AWC	<b>Project Type</b>	Completion
<b>Name of Executant</b>	Sarat Kumar Malla		

## Administrative Approval Details

<b>Approval No.</b>	OD/354/3380/117898/411379/00068310/AS
---------------------	---------------------------------------

## Technical Sanction Details

<b>Technical Sanction No.</b>	OD/354/3380/117898/411379/00068310/TS
<b>Fund Sanction No.</b>	7726
<b>Fund Sanction Amount (in Rs.)</b>	200000

## LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	26.9044765425	Sqm

	i	Semi-Skilled	0.6547619047619	17.616026307589	-
	ii	Skilled	0.6547619047619	17.616026307589	-
2		<b>R.C.C. Work (AR0410a) : Centring &amp; Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</b>	-	43.5158209418	Sqm
	i	Semi-Skilled	0.305555555555556	13.296500843328	-
	ii	Skilled	0.305555555555556	13.296500843328	-

3	<p><b>R.C.C. Work (AR0402a) : Reinforced cement concrete (1:11/2:3) work with 12mm size black hard hand broken granite chips -</b>  'Reinforced cement concrete (1:1.5:3) work with 12mm size black hard hand broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge. (To be used for minor repair work only)</p>	-	8.6419935732	Cum
i	Un-Skilled	4.6	39.75317043672	-
ii	Skilled	0.68	5.876555629776	-
4	<p><b>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b>  Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	8.62	Qntl

	i	Un-Skilled	0.8	6.896	-
	ii	Highly-Skilled	0.3	2.586	-
	iii	Semi-Skilled	0.044	0.37928	-
5		<b>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T &amp; P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</b>	-	24.89428788	Sqm
	i	Un-Skilled	0.17	4.2320289396	-
	ii	Skilled	0.14	3.4852003032	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Semi-Skilled	31.291807150917	512	16021.40526127
1	Skilled	40.274283083893	562	22634.147093148
2	Un-Skilled	50.88119937632	462	23507.11411186
3	Highly-Skilled	2.586	612	1582.632
<b>Total: 63745.298466277</b>				