

ESTIMATION DPR							
State	Odisha	District	Koraput	Block	Kundura	Gram Panchayat	Lima

Work Code	OD/363/3473/119837/429157/00070014 (CONST. OF PAVER BLOCK ROAD AT JHADESWAR TEMPLE, LIMA)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Kundura	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	Bikashita Gaon Bikashita Odisha	Scheme Component Name	Viksit Gaon Vikshit Odisha (VGVO)
Project Sub-Category	Pavor Block	Project Type	New Work
Name of Executant	PRATIBHA RANI PODHA		

Administrative Approval Details

Approval No.	OD/363/3473/119837/429157/00070014/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/363/3473/119837/429157/00070014/TS
Fund Sanction No.	4031
Fund Sanction Amount (in Rs.)	360442

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	10.33125	Cum

	i	Un-Skilled	0.516	5.330925	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	29.0175	Cum
	i	Un-Skilled	0.1236	3.586563	-
3		miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	248.85	Sqm

4	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	13.63725	Cum
i	Skilled	0.18	2.454705	-
ii	Un-Skilled	3.9	53.185275	-
5	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	2.06625	Cum
i	Un-Skilled	4.6	9.50475	-
ii	Skilled	0.68	1.40505	-

6	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	59.508	Sqm
i	Semi-Skilled	0.05	2.9754	-
ii	Skilled	0.05	2.9754	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	71.607513	462	33082.671006
1	Skilled	6.835155	562	3841.35711
2	Semi-Skilled	2.9754	512	1523.4048
Total:				38447.432916