

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Balasore	<b>Block</b>	Oupada	<b>Gram Panchayat</b>	Rairamachan drapur

<b>Work Code</b>	OD/346/3306/116263/393376/00071446 (Const of CC road from mahisadali sulochana Naik house to kedupada hata)
<b>Project Category</b>	Road

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Oupada	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	23-12-2025	<b>Date of Completion</b>	-
<b>Scheme Name</b>	Bikashita Gaon Bikashita Odisha	<b>Scheme Component Name</b>	Viksit Gaon Vikshit Odisha (VGVO)
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	New Work
<b>Name of Executant</b>	Sameer Kumar Rout		

### Administrative Approval Details

<b>Approval No.</b>	OD/346/3306/116263/393376/00071446/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/346/3306/116263/393376/00071446/TS
<b>Fund Sanction No.</b>	4599
<b>Fund Sanction Amount (in Rs.)</b>	400000

### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	3.6478660850016	Cum

	i	Un-Skilled	0.516	1.8822988998608	-
2		<b>Earth Work (AR0115)</b> <b>: Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	19.749714245363	Cum
	i	Un-Skilled	0.1236	2.4410646807269	-
3		<b>Concrete (AR0303a)</b> <b>: Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	27.11296646576	Cum
	i	Un-Skilled	3.9	105.74056921646	-
	ii	Skilled	0.18	4.8803339638368	-

4	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	21.58589664	Cum
i	Un-Skilled	4.6	99.295124544	-
ii	Skilled	0.68	14.6784097152	-
5	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	57.1667276334	Sqm
i	Semi-Skilled	0.05	2.85833638167	-
ii	Skilled	0.05	2.85833638167	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
--------	-------------	----------	------	--------

0	Un-Skilled	209.35905734105	462	96723.884491566
1	Skilled	22.417080060707	562	12598.398994117
2	Semi-Skilled	2.85833638167	512	1463.468227415
				<b>Total: 110785.7517131</b>