

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Cuttack	<b>Block</b>	Tigiria	<b>Gram Panchayat</b>	Panchagaon

<b>Work Code</b>	OD/350/3345/117176/398985/00073200 (Construction of CC Road from Santosh Kumar Singh Samant House to Sunil Das House ( Badal), Panchagaon)						
<b>Project Category</b>	Road						

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Tigiria	<b>Proposal Date</b>	30-11-2024
<b>Date of Commencement</b>	27-01-2026	<b>Date of Completion</b>	-
<b>Scheme Name</b>	SFC Devolution of Fund	<b>Scheme Component Name</b>	5TH SFC DEVOLUTION GRANT TO ZILLA PARISHAD
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	New Work
<b>Name of Executant</b>	Mihir Kumar Sethy		

### Administrative Approval Details

<b>Approval No.</b>	OD/350/3345/117176/398985/00073200/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/350/3345/117176/398985/00073200/TS
<b>Fund Sanction No.</b>	5132
<b>Fund Sanction Amount (in Rs.)</b>	150000

### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	20.99877	Cum
i	Un-Skilled	4.6	96.594342	-
ii	Skilled	0.68	14.2791636	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	96.594342	462	44626.586004
1	Skilled	14.2791636	562	8024.8899432
<b>Total: 52651.4759472</b>				