

ESTIMATION DPR							
State	Odisha	District	Angul	Block	Kaniha	Gram Panchayat	Deranga

Work Code	OD/344/3280/115674/403765/00075361 (Const. of Market Complex with 04 Nos. of Rooms)
Project Category	Building

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Kaniha	Proposal Date	-
Date of Commencement	02-02-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Market Complex	Project Type	New Work
Name of Executant	Ghanasyam Patel		

Administrative Approval Details

Approval No.	OD/344/3280/115674/403765/00075361/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/344/3280/115674/403765/00075361/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	42.988442	Cum

	i	Un-Skilled	0.516	22.182036072	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	51.0971558976	Cum
	i	Un-Skilled	0.1236	6.3156084689434	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	12.538342749683	Cum
	i	Skilled	0.18	2.2569016949429	-
	ii	Un-Skilled	3.9	48.899536723764	-

4	R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	5.858038	Cum
i	Un-Skilled	1.3333	7.8105220654	-
ii	Skilled	0.175	1.02515665	-
iii	Semi-Skilled	0.1323	0.7750184274	-

5	R.C.C. Work (AR0404Ab) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	2.703731671872	Cum
i	Un-Skilled	1.3333	3.6048854381069	-
ii	Skilled	0.35	0.9463060851552	-
iii	Semi-Skilled	0.3073	0.83085674276627	-

6	R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	3.8145278112	Cum
i	Un-Skilled	1.3333	5.085909930673	-
ii	Skilled	5.33875	20.364810352044	-
iii	Semi-Skilled	5.29605	20.201930014506	-

7	R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	2.07143196944	Cum
i	Un-Skilled	1.3333	2.7618402448544	-
ii	Skilled	2.34375	4.854918678375	-
iii	Semi-Skilled	2.30105	4.7664685332799	-

8	R.C.C. Work (AR0404Ag) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	8.88542106816	Cum
i	Un-Skilled	1.3333	11.846931910178	-
ii	Skilled	3.15525	28.035724825312	-
iii	Semi-Skilled	3.11255	27.656317345701	-

9	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	23.53	Qntl
i	Un-Skilled	0.8	18.824	-
ii	Highly-Skilled	0.3	7.059	-
iii	Semi-Skilled	0.044	1.03532	-
10	<p>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	15.17770993872	Cum

	i	Un-Skilled	2.96	44.926021418611	-
	ii	Skilled	1.05	15.936595435656	-
	iii	Highly-Skilled	0.35	5.312198478552	-
11		<p>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	24.99726117952	Cum
	i	Un-Skilled	2.96	73.991893091379	-
	ii	Skilled	1.05	26.247124238496	-
	iii	Highly-Skilled	0.35	8.749041412832	-

12	<p>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	57.785666	Sqm
i	Un-Skilled	0.17	9.82356322	-
ii	Skilled	0.14	8.08999324	-
13	<p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	-	115.15884268	Sqm
i	Un-Skilled	0.12	13.8190611216	-
ii	Skilled	0.14	16.1222379752	-

14	<p>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	122.15443858	Sqm
i	Un-Skilled	0.24	29.3170652592	-
ii	Skilled	0.16	19.5447101728	-
15	<p>miscellaneous (ARM031) : Labour for fitting and fixing-departmental shutters excluding cost of fixing and fitting Chaukath - Labour for fitting and fixing-departmental shutters excluding cost of fixing and fitting Chaukath but including mending size of grooves in chaukaths and size of shutters,etc. complete (Doors and Window) and as directed by Engineer-in-Charge.</p>	-	23.51560736	Sqm

16	Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in- charge.	-	5.33	Qntl
i	Un-Skilled	6.3976377952756	34.099409448819	-
ii	Semi-Skilled	1.9685039370079	10.492125984252	-
iii	Skilled	3.9370078740157	20.984251968504	-
iv	Highly-Skilled	3.4448818897638	18.361220472441	-
17	Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	53.697934	Sqm
i	Un-Skilled	0.36	19.33125624	-
ii	Highly-Skilled	0.13	6.98073142	-

18	Painting (AR0901bi) : First Floor - Priming one coat in outer surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	47.03121472	Sqm
	i Highly-Skilled	0.056451612903226	2.6549879277419	-
	ii Un-Skilled	0.056451612903226	2.6549879277419	-
19	Painting (AR0903i) : Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	47.03121472	Sqm
	i Highly-Skilled	0.13440860215054	6.321399827957	-
	ii Un-Skilled	0.11827956989247	5.5628318486022	-

20	Painting (AR0918ca) : Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	296.09	Sqm
i	Un-Skilled	0.11776344086022	34.868577204301	-
ii	Highly-Skilled	0.10776344086022	31.907677204301	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	395.72593763417	462	182825.38318699
1	Skilled	164.40873131648	562	92397.706999865
2	Semi-Skilled	65.758037047905	512	33668.114968528
3	Highly-Skilled	87.346256743825	612	53455.909127221
Total:				362347.1142826