

ESTIMATION DPR

State	Odisha	District	Dhenkanal	Block	Odapada	Gram Panchayat	Bangursingha
--------------	--------	-----------------	-----------	--------------	---------	-----------------------	--------------

Work Code	OD/352/3355/117390/402926/00077656 (Repair & Maintenance of Bangursingh Upper Primary School)
Project Category	Building

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Odapada	Proposal Date	-
Date of Commencement	25-01-2026	Date of Completion	06-02-2026
Scheme Name	Asset Management School and Mass Education Department	Scheme Component Name	Self/Personal Deposit
Project Sub-Category	Elementary School	Project Type	Repair and Maintenance
Name of Executant	Sadashiba Behera		

Administrative Approval Details

Approval No.	OD/352/3355/117390/402926/00077656/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/352/3355/117390/402926/00077656/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	200000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	-------------------------------------------	---------------------------	------

1	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	3.414	Cum
i	Skilled	0.18	0.61452	-
ii	Un-Skilled	3.9	13.3146	-
2	<p>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	2.49	Cum
i	Un-Skilled	2.96	7.3704	-

	ii	Skilled	1.05	2.6145	-
	iii	Highly-Skilled	0.35	0.8715	-
3		Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	141.98	Sqm
	i	Un-Skilled	0.24	34.0752	-
	ii	Skilled	0.16	22.7168	-
4		Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	48.875	Sqm
	i	Un-Skilled	0.17	8.30875	-

	ii	Skilled	0.14	6.8425	-
5		Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	2.2032	Qntl
	i	Un-Skilled	6.3976377952756	14.095275590551	-
	ii	Semi-Skilled	1.9685039370079	4.3370078740157	-
	iii	Skilled	3.9370078740157	8.6740157480315	-
	iv	Highly-Skilled	3.4448818897638	7.5897637795276	-
6		Other Building Items. (AR1902) : cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc. complete. and as per the direction of Engineer in Charge.	-	41.075	Sqm
	i	Un-Skilled	0.057	2.341275	-

	ii	Skilled	0.05	2.05375	-
7		Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	197.755	Sqm
	i	Highly-Skilled	0.053763440860215	10.631989247312	-
	ii	Un-Skilled	0.053763440860215	10.631989247312	-
8		Painting (AR0922) : Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	152.06	Sqm
	i	Highly-Skilled	0.052	7.90712	-
	ii	Un-Skilled	0.062	9.42772	-

9	Painting (AR0903b) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	10.98	Sqm
i	Highly-Skilled	0.18817204301075	2.0661290322581	-
ii	Un-Skilled	0.17204301075269	1.8890322580645	-
10	Painting (AR0918f) : Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside) - Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	50.375	Sqm
i	Un-Skilled	0.064	3.224	-
ii	Highly-Skilled	0.054	2.72025	-

11	<p>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	47.82	Sqm
i	Un-Skilled	0.216	10.32912	-
ii	Highly-Skilled	0.216	10.32912	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Skilled	43.516085748031	562	24456.040190394
1	Un-Skilled	115.00736209593	462	53133.401288319
2	Highly-Skilled	42.115872059097	612	25774.913700168
3	Semi-Skilled	4.3370078740157	512	2220.5480314961
Total:				105584.90321038