

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Baripada	Gram Panchayat	Laxmiposi

Work Code	OD/365/3490/120105/389222/00078452 (IMPROVMENT/MAINTENANCE OF ROAD FROM PWD DEULI ROAD TO BULU HOUSE AT KHATRAPATNA)
Project Category	Road

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Baripada	Proposal Date	-
Date of Commencement	28-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	MANASWINI DAS		

Administrative Approval Details

Approval No.	OD/365/3490/120105/389222/00078452/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/365/3490/120105/389222/00078452/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	147984

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	1.449	Cum

	i	Un-Skilled	0.516	0.747684	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.33175	Cum
	i	Un-Skilled	0.1236	1.0298043	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.78075	Cum
	i	Skilled	0.18	1.760535	-
	ii	Un-Skilled	3.9	38.144925	-

4	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	14.49	Sqm
i	Semi-Skilled	0.05	0.7245	-
ii	Skilled	0.05	0.7245	-
5	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	8.81475	Cum
i	Un-Skilled	4.6	40.54785	-
ii	Skilled	0.68	5.99403	-
SI.No.	Labour Type	Qty Unit	Rate	Amount

0	Un-Skilled	80.4702633	462	37177.2616446
1	Skilled	8.479065	562	4765.23453
2	Semi-Skilled	0.7245	512	370.944
				Total: 42313.4401746