

ESTIMATION DPR

State	Odisha	District	Khordha	Block	Bhubaneswar	Gram Panchayat	Dhauri
--------------	--------	-----------------	---------	--------------	-------------	-----------------------	--------

Work Code	OD/362/3460/119604/407760/00085859 (RETESTINGTENDER27-01-2000)
Project Category	Building

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Bhubaneswar	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Street Light
Project Sub-Category	GP Bhawan	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	3000000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
---------------	----------------------	--	----------------------------------	-------------

1	<p>Earth Work (AR0103a1) : Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m to 75m lead and 1.5m - Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per specification approved by the dept.</p>	-	88.49	Cum
	i Un-Skilled	0.7006	61.996094	-
2	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	434.946048	Cum
	i Skilled	0.18	78.29028864	-
	ii Un-Skilled	3.9	1696.2895872	-

3	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	240.804576	Sqm
i	Semi-Skilled	0.05	12.0402288	-
ii	Skilled	0.05	12.0402288	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	1758.2856812	462	812327.9847144
1	Skilled	90.33051744	562	50765.75080128
2	Semi-Skilled	12.0402288	512	6164.5971456
Total:				869258.33266128