

ESTIMATION DPR							
State	Odisha	District	Nayagarh	Block	Nayagarh	Gram Panchayat	Champatipur

Work Code	OD/367/3527/120660/406280/00013779 (DEV OF PATANASAH I & KADALIBASTA SMASAN ROAD)
Project Category	Road

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Nayagarh	Proposal Date	17-11-2023
Date of Commencement	22-04-2025	Date of Completion	27-05-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	Krushna Chandra Acharya		

Administrative Approval Details

Approval No.	OD/367/3527/120660/406280/00013779/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/367/3527/120660/406280/00013779/TS
Fund Sanction No.	404
Fund Sanction Amount (in Rs.)	131112

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	23.1	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	3.465	Cum
i)	BRM029 : Sand for filling and road blinding	1	3.465	1 Cum
3	Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	22.2075	Cum
i)	BRM340 : Cement	2.29	50.855175	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	10.6596	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	21.3192	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	0.4725	Cum
i)	BRM340 : Cement	3.23	1.526175	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.212625	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	0.42525	1 Cum.
5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	25.2	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.067284	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	3.1752	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	3.465	1 Cum	410.7	1423.0755
2	BRM340	52.38135	1 Qntl.	579.287	30343.83509745
3	BRM028	10.872225	1 Cum	417.13	4535.13121425
4	BRM045	21.3192	1 Cum.	1038.44	22138.710048
5	BRM056	0.42525	1 Cum.	1672.63	711.2859075
6	BRM104	0.067284	1Cum.	58573.086	3941.031518424
7	BRM092	3.1752	1Mtr.	229.106	727.4573712
					Total: 63820.526656824