

ESTIMATION DPR							
State	Odisha	District	Kendujhar	Block	Kendujhar Sadar	Gram Panchayat	Kathabari

Work Code	OD/361/3452/119457/386156/00014281 (CONSTRUCTION OF VANA SURAKHYA SAMITI BUILDING AT BARIGAON)
Project Category	Building

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Kendujhar Sadar	Proposal Date	-
Date of Commencement	18-07-2025	Date of Completion	-
Scheme Name	Construction of Vana Suraksha Samiti Building	Scheme Component Name	Construction of Buildings for Vana Suraksha Samiti
Project Sub-Category	Others	Project Type	New Work
Name of Executant	Subhashree Behera		

Administrative Approval Details

Approval No.	OD/361/3452/119457/386156/00014281/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/361/3452/119457/386156/00014281/TS
Fund Sanction No.	18481
Fund Sanction Amount (in Rs.)	850000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	28.27154692192	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.3023581127456	Cum
i)	BRM029 : Sand for filling and road blinding	1	9.3023581127456	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	6.8918890969056	Cum
i)	BRM340 : Cement	2.29	15.782426031914	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	3.3081067665147	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	6.6162135330294	1 Cum.

4	<p>R.C.C. Work (AR0404Aa) ∴ Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	4.057231104	Cum
i)	BRM340 : Cement	3.4733	14.091980793523	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.8257539968	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.46060319744	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.19090479616	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.01624921057152	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	0.766816678656	1Mtr.

5	R.C.C. Work (AR0404Ab) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	2.0738363206112	Cum
i)	BRM340 : Cement	3.4733	7.2030556923789	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.93322634427504	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.74658107542003	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.11987161313	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.02768571488016	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1.3065168819851	1Mtr.

6	<p>R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)</p>	-	3.7922000144	Cum
i)	BRM340 : Cement	3.4733	13.171448310016	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.70649000648	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.365192005184	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.047788007776	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	16.760007183642	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.15748627439802	1Cum.

7	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	1.16753422832	Cum
i)	BRM340 : Cement	3.4733	4.0551966352239	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.525390402744	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.4203123221952	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.6304684832928	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	4.4010202736522	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.086553398715161	1Cum.

8	R.C.C. Work (AR0404Ae) ∴Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Stairs excluding landing but including railing)	-	1.41208236064	Cum
i)	BRM340 : Cement	3.4733	4.9045856632109	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.635437062288	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.5083496498304	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.7625244747456	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	1.17	1.6521363619488	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.04806	0.067864678252358	1Cum.

9	<p>R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)</p>	-	5.388027541728	Cum
i)	BRM340 : Cement	3.4733	18.714236060684	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.4246123937776	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.9396899150221	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.9095348725331	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	33.522152153615	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.27057165666846	1Cum.

10	<p>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	7.354351372336	Cum
i)	BRM340 : Cement	0.672	4.9421241222098	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	2.0592183842541	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	2574.0229803176	1000 Nos
11	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	19.32293408288	Cum

i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	19.32293408288	1 Cum
ii)	BRM340 : Cement	0.672	12.985011703695	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	5.4104215432064	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	350	6763.026929008	1000 Nos
12	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	16.101	Qntl
i)	BRM162 : Binding Wire.	0.8	12.8808	1 Kg.
ii)	BRM341 : Steel	1.05	16.90605	1 Qntl.
13	Plastering (AR1017) :.20mm thick cement Plaster in CM (1:4) over masonry work in inside. - 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	40.287850465	Sqm

i)	BRM340 : Cement	0.0744	2.997416074596	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.846044859765	1 Cum
14	Plastering (AR1004i) :.12mm thick cement plaster (1:6) over Brick work in outside. - 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	117.6804344866	Sqm
i)	BRM340 : Cement	0.0358	4.2129595546203	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.765206517299	1 Cum
15	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	102.02235848	Sqm
i)	BRM340 : Cement	0.043	4.38696141464	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.83640245264	1 Cum

16	Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	43.33088823	Sqm
i)	BRM340 : Cement	0.0372	1.611909042156	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.324981661725	1 Cum
17	Flooring (AR0802i) :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	2.43870375	Sqm
i)	BRM340 : Cement	0.0858	0.20924078175	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.012	0.029264445	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	0.05609018625	1 Cum.

18	<p>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	27.3276497075	Sqm
i)	BRM174 : White Cement.	0.0076	0.207690137777	1Qntl
ii)	BRM340 : Cement	0.1074	2.9349895785855	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.5738806438575	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	27.3276497075	1 Sqm.

19	<p>Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	3.90935824	Sqm
i)	<p>BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)</p>	1	3.90935824	1 Sqm.
ii)	<p>BRMMR0027 : Wax Polish</p>	1	3.90935824	1 Sqm
iii)	<p>BRM340 : Cement</p>	0.1375	0.537536758	1 Qntl.
iv)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.0586403736	1 Cum

20	<p>Flooring (AR0816) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	3.251605	Sqm
i)	BRMMR0027 : Wax Polish	1	3.251605	1 Sqm
ii)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	3.251605	1 Sqm.
iii)	BRM340 : Cement	0.2737	0.8899642885	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.042270865	1 Cum

21	<p>Flooring (AR0817b) :.Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	8.175464	Sqm
i)	<p>BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753</p>	1	8.175464	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	1.1241263	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.12263196	1 Cum
22	<p>miscellaneous(ARM105) :.Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge. - Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge.</p>	-	11.77545525	Sqm
i)	<p>BRMM105 : Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works)</p>	1	11.77545525	Sqm

23	Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	3.4315	Qntl
i)	BRM341 : Steel	1	3.4315	1 Qntl.
24	Other Building Items. (AR1909) :.Al. door with OEL anodized Al. door section of 9202 as vertical member - Providing fitting, fixing of Al. door with OEL anodized Al. door section of 9202 as vertical member, 9201 as top member and 9200 as bottom and middle member and 12mm thick pre-laminated board fixed on door frame by means of tapered clip No. 4660 and the frame to be completed by means of jointing angle No.1855 including all cost of labour,T&P , hire charges of drilling machine, labour charges etc. complete. and as per direction of Engineer in Charge	-	1.6258025	Sqm
i)	BRM281 : Prelaminated particle board (standard type) (I.S.I.) 12mm	1.1018518518519	1.7913934953704	Sqm
ii)	BRMMR0008 : Hire charges of drills machine	0.6944444444444444	1.1290295138889	Day
iii)	BRMMR0018 : 6-Level mortice lock	0.46296296296296	0.75268634259259	Each
iv)	BRMMR0017 : Handle	0.92592592592593	1.5053726851852	Each
v)	BRMMR0016 : Door Stopper	0.46296296296296	0.75268634259259	Each
vi)	BRMMR0011 : U rubber beading	8.4675925925926	13.766633206019	Mtr
vii)	BRMMR0015 : 4 Anodised Al. Hinges	1.8518518518519	3.0107453703704	Each

viii)	BRM304 : Aluminium extruded section	11.821805555556	19.219921026736	kg
25	Painting(AR0918cb) :.Finishing wall two coats with weather coat with one coat waterbound Primer - Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	134.03859034	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	16.7548237925	1 Ltr
ii)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	12.106711385548	1 Ltr
26	Painting(AR0918d) :.Finishing wall with two coat water proofing cement paint including two coats cement wash on the inner surface of approved shade on old work(Inside) - Finishing wall with two coat water proofing cement paint including two coats cement wash on the inner surface of approved shade on old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Inside)	-	65.1528739	Sqm
i)	BRM143 : Cement paint	0.25	16.288218475	1 Kg.
ii)	BRM340 : Cement	0.016145161290323	1.0519036576435	1 Qntl.

27	Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	130.3057478	Sqm
i)	BRM142 : Distemper	0.25	32.57643695	1 Kg.
28	Painting(AR0903ak) :.Painting two coats of enamel paint with a coat of wood primer new wood work in inner surface paint (Inside)(For repair and maintenance) . - Painting two coats of enamel paint with a coat of wood primer in new wood work inner surface paint including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)(For repair and maintenance)	-	25.7399374375	Sqm
i)	BRM141 : Enamel paint	0.125	3.2174921796875	1 Litre
ii)	BRM138 : Wood Primer	0.075	1.9304953078125	1 Litre

29	Other Building Items. (AR1911) :Stainless steel of 304 grade in hand railing using 50mm dia of 2mm - Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge	-	6.095999804928	Rmt
i)	BRMMR0024 : Buffing, Polishing etc.	0.30674846625767	1.8699385904687	L.S.
ii)	BRMMR0023 : Fabrication	10.478527607362	63.877102250411	kg
iii)	BRMMR0022 : Stainless steel square pipe bracing of size 32mmx32mmx2mm in 3 rows	5.101226993865	31.097078759495	kg
iv)	BRMMR0021 : Balustrade of size 30mmx32mmx2mm	1.8773006134969	11.444024173669	kg
v)	BRMMR0020 : Railing 50mm outer dia of 2mm thick	3.5	21.335999317248	kg

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	9.3023581127456	1 Cum	1073.31	9984.313985991
2	BRM340	115.80707246335	1 Qntl.	602.137	69731.723191862
3	BRM028	24.427980679226	1 Cum	1083.31	26463.075749613
4	BRM044	6.6162135330294	1 Cum.	1466.56	9703.0741189996
5	BRM060	6.4407281650917	1 Cum.	1889.98	12172.84741746
6	BRM052	9.6610922476376	1 Cum.	1806.31	17450.92753783
7	BRM104	0.62641093348568	1Cum.	58573.086	36690.821478397
8	BRM092	2.0733335606411	1Mtr.	229.106	475.01315874423
9	BRM084	50.282159337257	1Mtr	250.166	12578.886672764
10	BRM094	6.053156635601	1Mtr.	240.106	1453.3992271476

11	BRM005	9337.0499093256	1000 Nos	6.30115	58834.152036147
12	BRMMR0025	19.32293408288	1 Cum	33	637.65682473504
13	BRM162	12.8808	1 Kg.	90.1	1160.56008
14	BRM341	20.33755	1 Qntl.	6667.087	135592.21521685
15	BRM056	0.05609018625	1 Cum.	1841.31	103.27942084399
16	BRM174	0.207690137777	1Qntl	2077.637	431.50471478059
17	BRM131	31.2370079475	1 Sqm.	670.4994451	20944.396495383
18	BRMMR0027	7.16096324	1 Sqm	8.5	60.86818754
19	BRM130	3.251605	1 Sqm.	469.4994451	1526.6267431844
20	BRM129	8.175464	1 Sqm.	424.6194451	3471.460987115
21	BRMM105	11.77545525	Sqm	16.22	190.997884155
22	BRM281	1.7913934953704	Sqm	710.82	1273.3583243792
23	BRMMR0008	1.1290295138889	Day	100	112.90295138889
24	BRMMR0018	0.75268634259259	Each	600	451.61180555556
25	BRMMR0017	1.5053726851852	Each	62.5	94.085792824074
26	BRMMR0016	0.75268634259259	Each	25	18.817158564815
27	BRMMR0011	13.766633206019	Mtr	15	206.49949809028
28	BRMMR0015	3.0107453703704	Each	39	117.41906944444
29	BRM304	19.219921026736	kg	297.97	5726.9598683366
30	BRM255	16.7548237925	1 Ltr	195.39457	3273.8015903613
31	BRM253	12.106711385548	1 Ltr	159.63457	1932.6496661461
32	BRM143	16.288218475	1 Kg.	48.43457	788.91285790268
33	BRM142	32.57643695	1 Kg.	70.70457	2303.3029666819
34	BRM141	3.2174921796875	1 Litre	205.94457	662.6250434241
35	BRM138	1.9304953078125	1 Litre	155.68457	300.54833188381
36	BRMMR0024	1.8699385904687	L.S.	178.42	333.63444331143
37	BRMMR0023	63.877102250411	kg	10	638.77102250411
38	BRMMR0022	31.097078759495	kg	256.62	7980.1323512615
39	BRMMR0021	11.444024173669	kg	256.62	2936.7654834468
40	BRMMR0020	21.335999317248	kg	240.24	5125.7604759757

Total: 453936.35983103