

ESTIMATION DPR							
State	Odisha	District	Deogarh	Block	Tileibani	Gram Panchayat	Dudhianali

Work Code	OD/351/3348/117227/383276/00014409 (Repair & Maintanance of Jamunali High school, Jamunali)
Project Category	Building

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Tileibani	Proposal Date	-
Date of Commencement	22-09-2025	Date of Completion	-
Scheme Name	Asset Management School and Mass Education Department	Scheme Component Name	Self/Personal Deposit
Project Sub-Category	Others	Project Type	Repair and Maintenance
Name of Executant	MANORANJAN BEHERA		

Administrative Approval Details

Approval No.	OD/351/3348/117227/383276/00014409/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/351/3348/117227/383276/00014409/TS
Fund Sanction No.	8559
Fund Sanction Amount (in Rs.)	248000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	10.602	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	2.964	Cum
i)	BRM029 : Sand for filling and road blinding	1	2.964	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	2.658	Cum
i)	BRM340 : Cement	2.29	6.08682	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	1.27584	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	2.55168	1 Cum.

4	<p>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	7.98	Cum
i)	BRM340 : Cement	0.672	5.36256	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	2.2344	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	2793	1000 Nos
5	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	12.19875	Cum

i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	12.19875	1 Cum
ii)	BRM340 : Cement	0.672	8.19756	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	3.41565	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	350	4269.5625	1000 Nos
6	R.C.C. Work (AR0404A) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	0.84	Cum
i)	BRM340 : Cement	3.4733	2.917572	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.378	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.3024	1 Cum.

iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.4536	1 Cum.
7	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	0.84	Cum
i)	BRM340 : Cement	3.4733	2.917572	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.378	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.3024	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.4536	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	3.16638	1Mtr.

vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.06227214	1Cum.
8	R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	2.414	Cum
i)	BRM340 : Cement	3.4733	8.3845462	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.0863	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.86904	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.30356	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	15.0189424	1Mtr

vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.1212243208	1Cum.
9	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	43.635	Sqm
i)	BRM340 : Cement	0.0358	1.562133	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.654525	1 Cum
10	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	30.24	Sqm
i)	BRM340 : Cement	0.043	1.30032	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	0.54432	1 Cum

11	<p>Flooring (AR0816) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	12.96	Sqm
i)	BRMMR0027 : Wax Polish	1	12.96	1 Sqm
ii)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	12.96	1 Sqm.
iii)	BRM340 : Cement	0.2737	3.547152	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.16848	1 Cum

12	Flooring (AR0817b) :.Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-		34.425	Sqm
i)	BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	1		34.425	1 Sqm.
ii)	BRM340 : Cement	0.1375		4.7334375	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.015		0.516375	1 Cum

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	2.964	1 Cum	331.46	982.44744
2	BRM340	45.0096727	1 Qntl.	571.902	25741.121836475
3	BRM028	10.65189	1 Cum	860.31	9163.9274859
4	BRM044	2.55168	1 Cum.	1596.76	4074.4205568
5	BRM005	7062.5625	1000 Nos	6.7429	47622.15268125
6	BRMMR0025	12.19875	1 Cum	33	402.55875
7	BRM060	1.47384	1 Cum.	2186.81	3223.0080504
8	BRM052	2.21076	1 Cum.	2179.1	4817.467116
9	BRM094	3.16638	1Mtr.	240.106	760.26683628
10	BRM104	0.1834964608	1Cum.	58573.086	10747.953979134
11	BRM084	15.0189424	1Mtr	250.166	3757.2287444384

12	BRMMR0027	12.96	1 Sqm	8.5	110.16
13	BRM130	12.96	1 Sqm.	467.8630561	6063.505207056
14	BRM129	34.425	1 Sqm.	422.9830561	14561.191706242
					Total: 132027.41038998