

ESTIMATION DPR							
State	Odisha	District	Nuapada	Block	Nuapada	Gram Panchayat	Godfula

Work Code	OD/368/3534/120839/421733/00014756 (Improvement of road from Tulsi Majhi house to Nartu Majhi House of Kala Bhera village)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Nuapada	Proposal Date	-
Date of Commencement	09-05-2025	Date of Completion	24-07-2025
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	Upgradation or Improvement
Name of Executant	Bhanu Pratap Dandsena		

Administrative Approval Details

Approval No.	OD/368/3534/120839/421733/00014756/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/368/3534/120839/421733/00014756/TS
Fund Sanction No.	15384
Fund Sanction Amount (in Rs.)	559505

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0110) :.Fine dressing of earth work in ordinary or hard soil in road formation - Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.	-	478.8	Sqm

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	47.88	Cum
i)	BRM029 : Sand for filling and road blinding	1	47.88	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	47.88	Cum
i)	BRM340 : Cement	2.29	109.6452	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	22.9824	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	45.9648	1 Cum.

4	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	45.22	Sqm
i)	<p>BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)</p>	0.00267	0.1207374	1Cum.
ii)	<p>BRM092 : Non-sal bullahs 75mm. mean dia of any length.</p>	0.126	5.69772	1Mtr.
5	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	35.91	Cum
i)	<p>BRM340 : Cement</p>	3.23	115.9893	1 Qntl.
ii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.45	16.1595	1 Cum
iii)	<p>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</p>	0.9	32.319	1 Cum.

6	Road Work (AR1307) :.Supplying & spreading moorum and consolidation with HRR - Supplying & spreading moorum and consolidation with HRR including cost, conveyance, royalty, taxes cost of all labour & material, hire charges of T & P materials required for work as per specification and complete as per direction of Engineer-in-Charge.	-	15.96	Cum
i)	BRM025 : Gravel or moorum	1.28	20.4288	1 Cum

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	47.88	1 Cum	413.05	19776.834
2	BRM340	225.6345	1 Qntl.	571.667	128987.7977115
3	BRM028	39.1419	1 Cum	417.99	16360.922781
4	BRM044	45.9648	1 Cum.	1271.26	58433.211648
5	BRM104	0.1207374	1Cum.	58573.086	7071.9621136164
6	BRM092	5.69772	1Mtr.	229.106	1305.38183832
7	BRM056	32.319	1 Cum.	1672.63	54057.72897
8	BRM025	20.4288	1 Cum	341.89	6984.402432
Total: 292978.24149444					