

ESTIMATION DPR							
State	Odisha	District	Angul	Block	Anugul	Gram Panchayat	Saradhapur

Work Code	OD/344/3276/115578/405104/00014986 (CONST OF VSS BUILDING AT BETAR)
Project Category	Building

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Anugul	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	Construction of Vana Suraksha Samiti Building	Scheme Component Name	Construction of Buildings for Vana Suraksha Samiti
Project Sub-Category	Vana Suraksha Samiti Building	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	4206
Fund Sanction Amount (in Rs.)	850000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	26.514	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	21.160985	Cum
i)	BRM029 : Sand for filling and road blinding	1	21.160985	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	6.71927	Cum
i)	BRM340 : Cement	2.29	15.3871283	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	3.2252496	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	6.4504992	1 Cum.

4	Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	9.33315	Cum
i)	BRM340 : Cement	0.672	6.2718768	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	2.613282	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	3266.6025	1000 Nos
5	R.C.C. Work (AR0407Aa) :.Column base (including centering & shuttering) - Column base (including centring & shuttering)	-	7.75575	Cum
i)	BRM340 : Cement	4.22	32.729265	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.4900875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.79207	1 Cum.

iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	4.188105	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.03106177875	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1.46583675	1Mtr.
6	R.C.C. Work (AR0407Ab) :.Plinth beam (including centering & shuttering) - Plinth beam (including centring & shuttering)	-	2.30625	Cum
i)	BRM340 : Cement	4.22	9.732375	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.0378125	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.83025	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.245375	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.0307884375	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1.4529375	1Mtr.
7	R.C.C. Work (AR0407Ac) :.Column & Beam (including centring & shuttering) - Column & Beam (including centring & shuttering)	-	3.375	Cum

i)	BRM340 : Cement	4.22	14.2425	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.51875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.215	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.8225	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	14.91615	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.140160375	1Cum.
8	R.C.C. Work (AR0407Ag) :.Roof (including centring & shuttering) - Roof (including centring & shuttering)	-	5.52	Cum
i)	BRM340 : Cement	4.22	23.2944	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.484	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.9872	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.9808	1 Cum.

v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	34.343232	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.277198944	1Cum.
9	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	1.284375	Cum
i)	BRM340 : Cement	3.4733	4.4610196875	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.57796875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.462375	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.6935625	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	4.8414515625	1Mtr.

vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.0952152140625	1Cum.
10	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	19.2	Qntl
i)	BRM162 : Binding Wire.	0.8	15.36	1 Kg.
ii)	BRM341 : Steel	1.05	20.16	1 Qntl.
11	Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	16.154375	Cum
i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	16.154375	1 Cum
ii)	BRM340 : Cement	0.672	10.85574	1 Qntl.

iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	4.523225	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance \pm 2 %	350	5654.03125	1000 Nos
12	Painting(AR0901ci) :.Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces(Outer surface) - Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	240.6217	Sqm
i)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	20.2122228	1 Ltr
13	Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	117.7365	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	14.7170625	1 Litre

14	Painting(AR0918ca) :.Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	90.7925	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	11.3490625	1 Ltr
ii)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	7.62657	1 Ltr
15	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	117.7365	Sqm
i)	BRM340 : Cement	0.043	5.0626695	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	2.119257	1 Cum
16	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	90.7925	Sqm

i)	BRM340 : Cement	0.0358	3.2503715	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.3618875	1 Cum
17	Flooring (AR0817aa) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.	-	15.458	Sqm
i)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	15.458	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	15.458	1 Sqm
iii)	BRM340 : Cement	0.1375	2.125475	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.23187	1 Cum

18	<p>Flooring (AR0816) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	32.0927	Sqm
i)	BRMMR0027 : Wax Polish	1	32.0927	1 Sqm
ii)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	32.0927	1 Sqm.
iii)	BRM340 : Cement	0.2737	8.78377199	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.4172051	1 Cum
19	<p>Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.</p>	-	3.8775	Qntl
i)	BRM341 : Steel	1	3.8775	1 Qntl.

20	Painting(AR0902a) :.Painting one coat of enamel paint with a coat of wood primer on new wood work in inner surface (inside) - Painting one coat of enamel paint with a coat of wood primer on new wood work in inner surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(inside).	-	16.43625	Sqm
i)	BRM141 : Enamel paint	0.075	1.23271875	1 Litre
ii)	BRM138 : Wood Primer	0.075	1.23271875	1 Litre

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	21.160985	1 Cum	933.85	19761.18584225
2	BRM340	136.1965927775	1 Qntl.	563.262	76714.36524104
3	BRM028	23.60059495	1 Cum	938.79	22156.002533111
4	BRM044	6.4504992	1 Cum.	1596.76	10299.899102592
5	BRM005	8920.63375	1000 Nos	6.31335	56319.083085563
6	BRM060	7.286895	1 Cum.	2006.73	14622.83080335
7	BRM052	10.9303425	1 Cum.	1983.8	21683.6134515
8	BRM104	0.5744247493125	1Cum.	58573.086	33645.83024201
9	BRM092	2.91877425	1Mtr.	229.106	668.7086933205
10	BRM084	49.259382	1Mtr	250.166	12323.022557412
11	BRM094	4.8414515625	1Mtr.	240.106	1162.4615688656
12	BRM162	15.36	1 Kg.	90.1	1383.936
13	BRM341	24.0375	1 Qntl.	6398.552	153805.1937
14	BRMMR0025	16.154375	1 Cum	33	533.094375
15	BRM252	27.8387928	1 Ltr	125.92622	3505.6339466672
16	BRM140	14.7170625	1 Litre	249.76622	3675.8250701288
17	BRM255	11.3490625	1 Ltr	195.21622	2215.5210817937
18	BRM131	15.458	1 Sqm.	665.5902781	10288.69451887
19	BRMMR0027	47.5507	1 Sqm	8.5	404.18095
20	BRM130	32.0927	1 Sqm.	464.5902781	14909.95641798
21	BRM141	1.23271875	1 Litre	205.76622	253.65187751063
22	BRM138	1.23271875	1 Litre	155.50622	191.69543313563

