

ESTIMATION DPR							
State	Odisha	District	Balangir	Block	Balangir	Gram Panchayat	Chudapali

Work Code	OD/345/3285/115785/420188/00015304 (Provision of facility centre at chudapali)
Project Category	Building

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Balangir	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant	Jyotranjan Mohanty		

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	20436
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0122Aia) ∴.Earthwork in all kinds of soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift - Earthwork in all kinds of soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge	-	46.3917674	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	32.58242293024	Cum
i)	BRM029 : Sand for filling and road blinding	1	32.58242293024	1 Cum
3	Masonry Stone Work (AR0717) :.Laterite stone masonry - Laterite stone masonry in cement mortar (1:6) in foundation and plinth cost conveyance, royalty, taxes of all materials, labor, required for the work, etc. complete and as per direction of the Engineer-in-charge.	-	4.813006496	Cum
i)	BRM340 : Cement	0.572	2.753039715712	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.24	1.15512155904	1 Cum
iii)	BRM079 : Laterite Stone rough dressed	1	4.813006496	1 Cum.

4	<p>R.C.C. Work (AR0404Aa) ∴ Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	21.708895956042	Cum
i)	BRM340 : Cement	3.4733	75.401508324121	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	9.7690031802189	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	7.8152025441751	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	11.722803816263	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.086944128303948	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	4.1029813356919	1Mtr.

5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	36.3016428634	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.096925386445278	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	4.5740070007884	1Mtr.
6	<p>R.C.C. Work (AR0410e) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</p>	-	15.82416799	Sqm
i)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	4.2603529203846	1Mtr.
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.083786940767564	1Cum.

7	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	16	Qntl
i)	BRM162 : Binding Wire.	0.8	12.8	1 Kg.
ii)	BRM341 : Steel	1.05	16.8	1 Qntl.
8	Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	21.16684622768	Cum
i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	21.16684622768	1 Cum
ii)	BRM340 : Cement	0.672	14.224120665001	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	5.9267169437504	1 Cum

iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	350	7408.396179688	1000 Nos
9	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	119.40532268125	Sqm
i)	BRM340 : Cement	0.0358	4.2747105519887	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.7910798402187	1 Cum
10	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	148.55363893125	Sqm
i)	BRM340 : Cement	0.043	6.3878064740437	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	2.6739655007625	1 Cum

11	<p>Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	3.7194273468	Sqm
i)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	3.7194273468	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	3.7194273468	1 Sqm
iii)	BRM340 : Cement	0.1375	0.511421260185	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.055791410202	1 Cum

12	<p>Flooring (AR0816j) :.Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 - Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	5.016762	Sqm
i)	BRM134 : Chequered Tiles.	1	5.016762	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	5.016762	1 Sqm
iii)	BRM340 : Cement	0.2737	1.3730877594	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.065217906	1 Cum
13	<p>Painting(AR0903i) :.Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)</p>	-	48.592043184375	Sqm
i)	BRM141 : Enamel paint	0.125	6.0740053980469	1 Litre
14	<p>Painting(AR0918Ai) :.Finishing wall one coat with weather coat - Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.</p>	-	110.61774404	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.075	8.296330803	1 Ltr

15	Painting(AR0919) :.Finishing wall One Coat with plastic emulsion paint of approved shades on old work (Inside) - Finishing wall One Coat with plastic emulsion paint of approved shades on old work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	53.6469488336	Sqm
i)	BRM140 : Plastic Emulsion paint	0.075	4.02352116252	1 Litre
16	R.C.C. Work (AR0410d) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	43.58358439	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	24.074741853524	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.2262195570719	1Cum.

17	<p>Flooring (AR0816) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	29.4670850236	Sqm
i)	BRMMR0027 : Wax Polish	1	29.4670850236	1 Sqm
ii)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	29.4670850236	1 Sqm.
iii)	BRM340 : Cement	0.2737	8.0651411709593	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.3830721053068	1 Cum

18	<p>Flooring (AR0817b) :.Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	55.18624006	Sqm
i)	<p>BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753</p>	1	55.18624006	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	7.58810800825	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.8277936009	1 Cum

19	<p>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	41.70601476	Sqm
i)	BRM174 : White Cement.	0.0076	0.316965712176	1Qntl
ii)	BRM340 : Cement	0.1074	4.479225985224	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.87582630996	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	41.70601476	1 Sqm.
20	<p>Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	-	317.077939	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	26.634546876	1 Ltr

21	Concrete (AR0304) :.Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal - Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-		13.940612546253	Cum
i)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96		13.382988044403	1 Cum.
ii)	BRM340 : Cement	1.72		23.977853579555	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.48		6.6914940222014	1 Cum
22	R.C.C. Work (AR0410a) :.Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-		82.72919247	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.6222222222222222		51.475941981333	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222		0.41548438884933	1Cum.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	32.58242293024	1 Cum	413.05	13458.169791336

2	BRM340	149.03602349444	1 Qntl.	534.912	79721.157399458
3	BRM028	30.215082378561	1 Cum	417.99	12629.602283415
4	BRM079	4.813006496	1 Cum.	1103.66	5311.9227493754
5	BRM060	7.8152025441751	1 Cum.	1741.11	13607.127301689
6	BRM052	11.722803816263	1 Cum.	1723.4	20203.080096947
7	BRM104	0.90936040143803	1Cum.	58573.086	53264.044998424
8	BRM092	8.6769883364803	1Mtr.	229.106	1987.9500898177
9	BRM094	4.2603529203846	1Mtr.	240.106	1022.9362983019
10	BRM162	12.8	1 Kg.	90	1152
11	BRM341	16.8	1 Qntl.	6218.022	104462.7696
12	BRMMR0025	21.16684622768	1 Cum	33	698.50592551344
13	BRM005	7408.396179688	1000 Nos	6.1539	45590.529250182
14	BRM131	45.4254421068	1 Sqm.	665.5902781	30234.73264468
15	BRMMR0027	38.2032743704	1 Sqm	8.5	324.7278321484
16	BRM134	5.016762	1 Sqm.	254.75	1278.0201195
17	BRM141	6.0740053980469	1 Litre	205.76622	1249.8251310157
18	BRM255	8.296330803	1 Ltr	195.21622	1619.5783392312
19	BRM140	4.02352116252	1 Litre	249.76622	1004.9396718526
20	BRM084	75.550683834857	1Mtr	250.166	18900.212372231
21	BRM130	29.4670850236	1 Sqm.	464.5902781	13690.121225911
22	BRM129	55.18624006	1 Sqm.	419.7102781	23162.232162876
23	BRM174	0.316965712176	1Qntl	2041.967	647.23352439489
24	BRM253	26.634546876	1 Ltr	159.45622	4247.0441662598
25	BRM044	13.382988044403	1 Cum.	1336.36	17884.489903018
Total: 467352.95287758					