

ESTIMATION DPR							
State	Odisha	District	Cuttack	Block	Niali	Gram Panchayat	Niali

Work Code	OD/350/3341/117065/400347/00017316 (Improvement of road from PwD main road to Kuanri Sahi)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Niali	Proposal Date	-
Date of Commencement	08-05-2025	Date of Completion	30-07-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	Upgradation or Improvement
Name of Executant	PRITI CHANDRIKA SAMAL		

Administrative Approval Details

Approval No.	OD/350/3341/117065/400347/00017316/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/350/3341/117065/400347/00017316/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	450000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	0.243	Cum

i)	BRM340 : Cement	2.29	0.55647	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	0.11664	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	0.23328	1 Cum.
2	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	55.115	Cum
i)	BRM340 : Cement	3.23	178.02145	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	24.80175	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	49.6035	1 Cum.

3	R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	45.3	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.120951	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	5.7078	1Mtr.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM340	178.57792	1 Qntl.	569.712	101737.98395904
2	BRM028	24.91839	1 Cum	548.19	13660.0122141
3	BRM044	0.23328	1 Cum.	2176.31	507.6895968
4	BRM056	49.6035	1 Cum.	2604.91	129212.653185
5	BRM104	0.120951	1Cum.	58573.086	7084.473324786
6	BRM092	5.7078	1Mtr.	229.106	1307.6912268
Total: 253510.50350653					