

ESTIMATION DPR							
State	Odisha	District	Ganjam	Block	Polosara	Gram Panchayat	Banthapalli

Work Code	OD/354/3380/117899/411493/00017556 (Repair and Maintenance of Primary School of K Muktamaladeipur PS)
Project Category	Building

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Polosara	Proposal Date	03-12-2024
Date of Commencement	14-11-2025	Date of Completion	19-11-2025
Scheme Name	Asset Management School and Mass Education Department	Scheme Component Name	Self/Personal Deposit
Project Sub-Category	Elementary School	Project Type	Repair and Maintenance
Name of Executant	Subhasmita Patro		

Administrative Approval Details

Approval No.	OD/354/3380/117899/411493/00017556/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3380/117899/411493/00017556/TS
Fund Sanction No.	11572
Fund Sanction Amount (in Rs.)	150000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	miscellaneous(ARM12 2) :.Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge. - Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.	-	224.174939	Sqm

i)	BRMM122 : Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting)	1	224.174939	Sqm
2	Other Building Items. (AR1902) :.cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc. complete. and as per the direction of Engineer in Charge.	-	332.778546	Sqm
i)	BRMMR0038 : Cement based putty	0.8	266.2228368	kg
3	miscellaneous(ARM287) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	7.6644975	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03	0.229934925	1 Cum

ii)	BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	7.6644975	1 Sqm
4	Painting(AR0901di) :.Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface) - Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	624.1595152	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	56.375698147097	1 Ltr
5	Painting(AR0920k) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)(For Repair and maintenance) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For Repair and maintenance)	-	273.227723	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	34.153465375	1 Litre

6	Painting(AR0918f) :.Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside) - Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	350.9317922	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	43.866474025	1 Ltr

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRMM122	224.174939	Sqm	5.12	1147.77568768
2	BRMMR0038	266.2228368	kg	30	7986.685104
3	BRM029	0.229934925	1 Cum	403.97	92.88681165225
4	BRMM287	7.6644975	1 Sqm	608.4	4663.080279
5	BRM253	56.375698147097	1 Ltr	159.33732	8982.7526558874
6	BRM140	34.153465375	1 Litre	249.64732	8526.3210995815
7	BRM255	43.866474025	1 Ltr	195.09732	8558.2315201271
Total: 39957.733157928					