

ESTIMATION DPR							
State	Odisha	District	Angul	Block	Chhendipada	Gram Panchayat	Tentuli Kodasahi

Work Code	OD/344/3279/115663/404486/00018060 (Maintenance of Jatrapadia to Jamunali Banka House Road with CC / Gr-II Metalling)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Chhendipada	Proposal Date	-
Date of Commencement	07-08-2025	Date of Completion	09-09-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	Repair and Maintenance
Name of Executant	AJIT KUMAR NAYAK		

Administrative Approval Details

Approval No.	OD/344/3279/115663/404486/00018060/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/344/3279/115663/404486/00018060/TS
Fund Sanction No.	31142
Fund Sanction Amount (in Rs.)	250000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	1.76	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	14.144	Cum
i)	BRM029 : Sand for filling and road blinding	1	14.144	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.29344	Cum
i)	BRM340 : Cement	2.29	37.3119776	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	7.8208512	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	15.6417024	1 Cum.

4	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	19.2	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.051264	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	2.4192	1Mtr.
5	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	13.71392	Cum
i)	BRM340 : Cement	3.23	44.2959616	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	6.171264	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	12.342528	1 Cum.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	14.144	1 Cum	933.85	13208.3744
2	BRM340	81.6079392	1 Qntl.	538.472	43943.590236902
3	BRM028	13.9921152	1 Cum	938.79	13135.657828608
4	BRM044	15.6417024	1 Cum.	2087.16	32646.735581184
5	BRM104	0.051264	1Cum.	58573.086	3002.690680704
6	BRM092	2.4192	1Mtr.	229.106	554.2532352
7	BRM056	12.342528	1 Cum.	2488.53	30714.75120384
					Total: 137206.05316644