

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Kalahandi	<b>Block</b>	Kesinga	<b>Gram Panchayat</b>	Laitara

<b>Work Code</b>	OD/358/3416/118756/422339/00020279 (Provision of Facility Centre at GP Hqrs Laitara GP)
<b>Project Category</b>	Building

<b>Financial Year</b>	2023-24	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Kesinga	<b>Proposal Date</b>	26-02-2024
<b>Date of Commencement</b>	04-10-2025	<b>Date of Completion</b>	28-11-2025
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Provision of Facilities at GP Head Quarter
<b>Project Sub-Category</b>	GP Facility Centre	<b>Project Type</b>	New Work
<b>Name of Executant</b>	TRILOCHAN BEHERA		

### Administrative Approval Details

<b>Approval No.</b>	OD/358/3416/118756/422339/00020279/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/358/3416/118756/422339/00020279/TS
<b>Fund Sanction No.</b>	4453
<b>Fund Sanction Amount (in Rs.)</b>	1000000

### MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>21.564</b>	Cum

2	<b>Earth Work (AR0115)</b> :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>28.3395</b>	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	28.3395	1 Cum
3	<b>Concrete (AR0303)</b> :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>6.56075</b>	Cum
i)	<b>BRM340</b> : Cement	2.29	15.0241175	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	3.14916	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	6.29832	1 Cum.

4	<p><b>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth</b>  - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance <math>\pm 8</math> percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	10.600325	Cum
i)	<b>BRM340</b> : Cement	0.672	7.1234184	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	2.968091	1 Cum
iii)	<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	3710.11375	1000 Nos
5	<p><b>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b>  Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance <math>\pm 8</math> percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	22.07875	Cum

i)	<b>BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK</b>	1	22.07875	1 Cum
ii)	<b>BRM340 : Cement</b>	0.672	14.83692	1 Qntl.
iii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.28	6.18205	1 Cum
iv)	<b>BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance <math>\pm</math> 2 %</b>	350	7727.5625	1000 Nos
6	<b>R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	<b>21.384</b>	Qntl
i)	<b>BRM162 : Binding Wire.</b>	0.8	17.1072	1 Kg.
ii)	<b>BRM341 : Steel</b>	1.05	22.4532	1 Qntl.

7	<b>Concrete (AR0317) :.2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips - 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge. (new work)</b>	-	<b>69.3</b>	Sqm
i)	<b>BRM340 : Cement</b>	0.1208	8.37144	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.0169	1.17117	1 Cum
iii)	<b>BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.</b>	0.0169	1.17117	1 Cum.
8	<b>Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</b>	-	<b>118.8625</b>	Sqm
i)	<b>BRM340 : Cement</b>	0.043	5.1110875	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.018	2.139525	1 Cum

9	<b>Plastering (AR1004)</b> :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	47.25	Sqm
i)	<b>BRM340</b> : Cement	0.0358	1.69155	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	0.70875	1 Cum
10	<b>Plastering (AR1008)</b> :.20mm thick cement Plaster in CM (1:6) over brick work in inside. - 20mm thick cement Plaster in CM (1:6) for stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp. and as per direction of Engineer-in-charge.	-	11.64	Sqm
i)	<b>BRM340</b> : Cement	0.057	0.66348	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.021	0.24444	1 Cum

11	<p><b>Flooring (AR0816)</b>  <b>:.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor -</b> Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	54.7336	Sqm
i)	<b>BRMMR0027</b> : Wax Polish	1	54.7336	1 Sqm
ii)	<b>BRM130</b> : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	54.7336	1 Sqm.
iii)	<b>BRM340</b> : Cement	0.2737	14.98058632	1 Qntl.
iv)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.013	0.7115368	1 Cum

12	<b>Other Building Items. (AR1901Ba) :.Vitrified Tile 600mmx600mm Coloured /Printed -</b> Supplying, fitting & fixing Vitrified Tile 600mmx600mm Coloured /Printed series(Homogeneous) in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all work all materials, taxes, labor, T&P , etc. complete as per direction of Engineer-in-charge.	-		<b>41.355</b>	Sqm
i)	<b>BRM132</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Coloured / Printed series(Homogeneous)	1		41.355	1 Sqm.
ii)	<b>BRM174</b> : White Cement.	0.0076		0.314298	1Qntl
iii)	<b>BRM340</b> : Cement	0.1074		4.441527	1 Qntl.
iv)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.021		0.868455	1 Cum
13	<b>Painting(AR0905a) :.Painting two coats of enamel paint with a coat of wood primer on old wood work in inner surface paint (Inside) -</b> Painting two coats of enamel paint with a coat of wood primer on old wood work in inner surface paint including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)	-		<b>15.405</b>	Sqm
i)	<b>BRM141</b> : Enamel paint	0.125		1.925625	1 Litre
ii)	<b>BRM138</b> : Wood Primer	0.075		1.155375	1 Litre

14	<p><b>Other Building Items. (AR1902) :.cement based wall putty (water based) -</b>  Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&amp;P,etc.co mplete. and as per the direction of Engineer in Charge.</p>	-	242.096	Sqm
i)	<b>BRMMR0038</b> : Cement based putty	0.8	193.6768	kg
15	<p><b>Painting(AR0901a) :.Priming one coat in inner surface with primer of approved quality over woodwork -</b> Priming one coat in inner surface with primer of approved quality over woodwork including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in-charge.</p>	-	393.35125	Sqm
i)	<b>BRM138</b> : Wood Primer	0.075	29.50134375	1 Litre
16	<p><b>Iron Work(AR1704) :.Iron Doors and windows fixing -</b>  Supplying, fitting &amp; fixing of Mild steel and put up for frames &amp; shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T &amp; P required for the work etc. as per direction of Engineer-in-charge.</p>	-	1.224	Qntl
i)	<b>BRM341</b> : Steel	1	1.224	1 Qntl.

17	<b>Painting(AR0920)</b> <b>:.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) -</b> Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	<b>242.096</b>	Sqm
i)	<b>BRM140</b> : Plastic Emulsion paint	0.125	30.262	1 Litre
18	<b>Painting(AR0918Ai)</b> <b>:.Finishing wall one coat with weather coat -</b> Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-	<b>128.87875</b>	Sqm
i)	<b>BRM255</b> : Weather Coat (I.S.I.)	0.075	9.66590625	1 Ltr
19	<b>R.C.C. Work (AR0404A)</b> <b>:.Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	<b>24.3102175</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	84.43667844275	1 Qntl.

ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	10.939597875	1 Cum
iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	8.7516783	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	13.12751745	1 Cum.
20	<b>R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</b>	-	<b>6.804</b>	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.01816668	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	0.857304	1Mtr.

21	<b>R.C.C. Work (AR0410d) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm</b>	-	<b>52.247</b>	Sqm
i)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	28.860247619048	1Mtr
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.27118680952381	1Cum.
22	<b>R.C.C. Work (AR0410e) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</b>	-	<b>12.3525</b>	Sqm
i)	<b>BRM094</b> : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	3.3256730769231	1Mtr.
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.065404903846154	1Cum.

23	<b>R.C.C. Work (AR0410a) :-Centring &amp; Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</b>	-	<b>58.525</b>	Sqm
i)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.6222222222222222	36.41555555555556	1Mtr
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.2939255555555556	1Cum.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	28.3395	1 Cum	347.95	9860.729025
2	<b>BRM340</b>	156.68080516275	1 Qntl.	601.645	94266.223022143
3	<b>BRM028</b>	29.082775675	1 Cum	352.89	10263.020707951
4	<b>BRM044</b>	6.29832	1 Cum.	1466.56	9236.8641792
5	<b>BRM005</b>	11437.67625	1000 Nos	6.4484	73754.7115305
6	<b>BRMMR0025</b>	22.07875	1 Cum	33	728.59875
7	<b>BRM162</b>	17.1072	1 Kg.	90.1	1541.35872
8	<b>BRM341</b>	23.6772	1 Qntl.	5281.395	125048.645694
9	<b>BRM064</b>	1.17117	1 Cum.	1321.51	1547.7128667
10	<b>BRMMR0027</b>	54.7336	1 Sqm	8.5	465.2356
11	<b>BRM130</b>	54.7336	1 Sqm.	460.3356667	25195.828246891
12	<b>BRM132</b>	41.355	1 Sqm.	706.0156667	29197.277896378
13	<b>BRM174</b>	0.314298	1Qntl	2044.345	642.53354481
14	<b>BRM141</b>	1.925625	1 Litre	205.61165	395.93093353125
15	<b>BRM138</b>	30.65671875	1 Litre	155.35165	4762.5718413984
16	<b>BRMMR0038</b>	193.6768	kg	30	5810.304
17	<b>BRM140</b>	30.262	1 Litre	249.61165	7553.7477523
18	<b>BRM255</b>	9.66590625	1 Ltr	189.77165	1834.3149778078

19	<b>BRM060</b>	8.7516783	1 Cum.	1866.31	16333.344728073
20	<b>BRM052</b>	13.12751745	1 Cum.	1851.31	24303.104330359
21	<b>BRM104</b>	0.64868394892552	1Cum.	58573.086	37995.420727234
22	<b>BRM092</b>	0.857304	1Mtr.	229.106	196.413490224
23	<b>BRM084</b>	65.275803174603	1Mtr	250.166	16329.786576978
24	<b>BRM094</b>	3.3256730769231	1Mtr.	240.106	798.51405980769
<b>Total: 498062.19320129</b>					