

ESTIMATION DPR							
State	Odisha	District	Khordha	Block	Balipatna	Gram Panchayat	Alisisasan

Work Code	OD/362/3457/275278/407671/00021169 (Provision Of Facility Centre At Alisisasan GP Hqrs)
Project Category	Building

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Balipatna	Proposal Date	-
Date of Commencement	08-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant	Sushree		

Administrative Approval Details

Approval No.	OD/362/3457/275278/407671/00021169/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/362/3457/275278/407671/00021169/TS
Fund Sanction No.	15219
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	25.559876352	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	28.796486592	Cum
i)	BRM029 : Sand for filling and road blinding	1	28.796486592	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.72913145088	Cum
i)	BRM340 : Cement	2.29	22.279711022515	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.6699830964224	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	9.3399661928448	1 Cum.

4	<p>R.C.C. Work (AR0404Aa) ∴ Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	5.1288804	Cum
i)	BRM340 : Cement	3.4733	17.81414029332	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.30799618	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.846396944	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.769595416	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.020541166002	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	0.9693583956	1Mtr.

5	R.C.C. Work (AR0404Ab) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	3.7404935376	Cum
i)	BRM340 : Cement	3.4733	12.991856204146	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.68322209192	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.346577673536	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.019866510304	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.04993558872696	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	2.356510928688	1Mtr.

6	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	6.77360721816	Cum
i)	BRM340 : Cement	3.4733	23.526769950835	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.048123248172	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.4384985985376	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	3.6577478978064	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	29.93663446138	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.28130113416297	1Cum.

7	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	1.3355547928	Cum
i)	BRM340 : Cement	3.4733	4.6387824618322	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.60099965676	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.480799725408	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.721199588112	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	5.0343737914596	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.099009351232039	1Cum.

8	R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	8.35855868736	Cum
i)	BRM340 : Cement	3.4733	29.031781888807	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.761351409312	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	3.0090811274496	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	4.5136216911744	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	52.003608729279	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.41974341331489	1Cum.

9	<p>R.C.C. Work (AR0404Af) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Sun sheds & Chajja)</p>	-	5.17098098	Sqm
i)	BRM340 : Cement	0.21708125	1.1225230148646	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.028125	0.1454338400625	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.0225	0.11634707205	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.03375	0.174520608075	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.68432	3.5386057042336	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00552344	0.028561603184171	1Cum.

10	<p>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	3.3140093423104	Cum
i)	BRM340 : Cement	0.672	2.2270142780326	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	0.92792261584691	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1159.9032698086	1000 Nos
11	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	20.0574124096	Cum

i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	20.0574124096	1 Cum
ii)	BRM340 : Cement	0.672	13.478581139251	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	5.616075474688	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	350	7020.09434336	1000 Nos
12	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	26	Qntl
i)	BRM162 : Binding Wire.	0.8	20.8	1 Kg.
ii)	BRM341 : Steel	1.05	27.3	1 Qntl.
13	Plastering (AR1017) :.20mm thick cement Plaster in CM (1:4) over masonry work in inside. - 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	65.29315743	Sqm

i)	BRM340 : Cement	0.0744	4.857810912792	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.021	1.37115630603	1 Cum
14	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	94.44611883	Sqm
i)	BRM340 : Cement	0.043	4.06118310969	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.70003013894	1 Cum
15	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	77.15779956	Sqm
i)	BRM340 : Cement	0.0358	2.762249224248	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.1573669934	1 Cum

16	Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	67.5869325	Sqm
i)	BRM340 : Cement	0.0372	2.514233889	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.50690199375	1 Cum
17	Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.	-	49.204680405	Sqm
i)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	49.204680405	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	49.204680405	1 Sqm

iii)	BRM340 : Cement	0.1375	6.7656435556875	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.738070206075	1 Cum
18	Flooring (AR0816) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	3.8859281034	Sqm
i)	BRMMR0027 : Wax Polish	1	3.8859281034	1 Sqm
ii)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	3.8859281034	1 Sqm.
iii)	BRM340 : Cement	0.2737	1.0635785219006	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.0505170653442	1 Cum

19	<p>Flooring (AR0817b) :.Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	34.89808292	Sqm
i)	<p>BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753</p>	1	34.89808292	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	4.7984864015	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.5234712438	1 Cum
20	<p>Painting(AR0918cb) :.Finishing wall two coats with weather coat with one coat waterbound Primer - Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)</p>	-	78.42685454	Sqm
i)	<p>BRM255 : Weather Coat (I.S.I.)</p>	0.125	9.8033568175	1 Ltr

ii)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	7.0837158939355	1 Ltr
21	Painting(AR0901c) :.Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	67.77831268	Sqm
i)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	5.69337826512	1 Ltr
22	Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	121.24584724	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	15.155730905	1 Litre
23	Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	3.36	Qntl
i)	BRM341 : Steel	1	3.36	1 Qntl.

24	Painting(AR0903b) :.Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	20.159951	Sqm
i)	BRM137 : Red oxide Primer	0.054	1.088637354	1 Litre
ii)	BRM141 : Enamel paint	0.125	2.519993875	1 Litre

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	28.796486592	1 Cum	397.3	11440.844123002
2	BRM340	153.93434586842	1 Qntl.	569.387	87648.215390984
3	BRM028	28.808621560523	1 Cum	403.69	11629.752437768
4	BRM044	9.3399661928448	1 Cum.	2087.16	19494.003839058
5	BRM060	9.2377011409812	1 Cum.	2489.58	22997.996006564
6	BRM052	13.856551711472	1 Cum.	2474.2	34283.880244524
7	BRM104	0.89909225662303	1Cum.	58573.086	52662.608069115
8	BRM092	3.325869324288	1Mtr.	229.106	761.97661741033
9	BRM084	85.478848894893	1Mtr	250.166	21383.90171264
10	BRM094	5.0343737914596	1Mtr.	240.106	1208.7833535722
11	BRM005	8179.9976131686	1000 Nos	6.30115	51543.391960218
12	BRMMR0025	20.0574124096	1 Cum	33	661.8946095168
13	BRM162	20.8	1 Kg.	90.1	1874.08
14	BRM341	30.66	1 Qntl.	6216.787	190606.68942
15	BRM131	49.204680405	1 Sqm.	660.6811111	32508.602921296
16	BRMMR0027	53.0906085084	1 Sqm	8.5	451.2701723214
17	BRM130	3.8859281034	1 Sqm.	459.6811111	1786.2877482256
18	BRM129	34.89808292	1 Sqm.	414.8011111	14475.763570476
19	BRM255	9.8033568175	1 Ltr	193.07787	1892.8112531729
20	BRM253	7.0837158939355	1 Ltr	154.51787	1094.5606916161
21	BRM252	5.69337826512	1 Ltr	125.74787	715.93018994314
22	BRM140	15.155730905	1 Litre	249.58787	3782.6865948721
23	BRM137	1.088637354	1 Litre	142.94787	155.61839095674

24	BRM141	2.519993875	1 Litre	205.58787	518.0801731743
					Total: 565579.62949042