

ESTIMATION DPR							
State	Odisha	District	Jajpur	Block	Dharmasala	Gram Panchayat	Arabal

Work Code	OD/356/3397/118328/401322/00022332 (Imp. of Road with CC/ Gr-II Metalling from Kangali Samal House to School Chhak At-Arabal)						
Project Category	Road						

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Dharmasala	Proposal Date	-
Date of Commencement	30-10-2025	Date of Completion	19-11-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	MONALISHA NAYAK		

Administrative Approval Details

Approval No.	OD/356/3397/118328/401322/00022332/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/356/3397/118328/401322/00022332/TS
Fund Sanction No.	31142
Fund Sanction Amount (in Rs.)	300000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	20.435	Cum
i)	BRM340 : Cement	2.29	46.79615	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	9.8088	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	19.6176	1 Cum.
2	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	24.4	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.065148	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	3.0744	1Mtr.

3	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	20.435	Cum
i)	BRM340 : Cement	3.23	66.00505	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	9.19575	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	18.3915	1 Cum.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM340	112.8012	1 Qntl.	595.447	67167.1361364
2	BRM028	19.00455	1 Cum	613.29	11655.3004695
3	BRM044	19.6176	1 Cum.	1802.51	35360.920176
4	BRM104	0.065148	1Cum.	58763.326	3828.313162248
5	BRM092	3.0744	1Mtr.	419.346	1289.2373424
6	BRM056	18.3915	1 Cum.	2248.31	41349.793365
Total: 160650.70065155					