

ESTIMATION DPR							
State	Odisha	District	Nuapada	Block	Sinapali	Gram Panchayat	Kusumjore

Work Code	OD/368/3535/120867/422254/00025804 (Construction of C.C Road from Brahmaniguda Banjarapada Rice Mill to Jampada Road)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Sinapali	Proposal Date	-
Date of Commencement	22-07-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	Sangram Keshari Parida		

Administrative Approval Details

Approval No.	OD/368/3535/120867/422254/00025804/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/368/3535/120867/422254/00025804/TS
Fund Sanction No.	193
Fund Sanction Amount (in Rs.)	200000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	1.12125	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	10.166	Cum
i)	BRM029 : Sand for filling and road blinding	1	10.166	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	13.9035	Cum
i)	BRM340 : Cement	2.29	31.839015	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	6.67368	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	13.34736	1 Cum.

4	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	35.88	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0957996	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	4.52088	1Mtr.
5	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	4.5	Qntl
i)	BRM162 : Binding Wire.	0.8	3.6	1 Kg.
ii)	BRM341 : Steel	1.05	4.725	1 Qntl.

6	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	10.9135	Cum
i)	BRM340 : Cement	3.23	35.250605	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	4.911075	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	9.82215	1 Cum.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	10.166	1 Cum	347.95	3537.2597
2	BRM340	67.08962	1 Qntl.	519.969	34884.52262178
3	BRM028	11.584755	1 Cum	483.09	5596.47929295
4	BRM044	13.34736	1 Cum.	1401.46	18705.7911456
5	BRM104	0.0957996	1Cum.	58573.086	5611.2782095656
6	BRM092	4.52088	1Mtr.	229.106	1035.76073328
7	BRM162	3.6	1 Kg.	90.1	324.36
8	BRM341	4.725	1 Qntl.	5595.287	26437.731075
9	BRM056	9.82215	1 Cum.	1802.83	17707.6666845
Total: 113840.84946268					