

ESTIMATION DPR							
State	Odisha	District	Angul	Block	Palalahada	Gram Panchayat	Nizigarh

Work Code	OD/344/3282/115729/403538/00029302 (Construction of CC road at Sasan Sahi Gadhuaghata)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Palalahada	Proposal Date	25-05-2023
Date of Commencement	25-07-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	SANJIB KUMAR MAHANTA		

Administrative Approval Details

Approval No.	OD/344/3282/115729/403538/00029302/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/344/3282/115729/403538/00029302/TS
Fund Sanction No.	11360
Fund Sanction Amount (in Rs.)	200000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	18.912122386886	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.4238423100864	Cum
i)	BRM029 : Sand for filling and road blinding	1	9.4238423100864	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	19.110082105789	Cum
i)	BRM340 : Cement	2.29	43.762088022257	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	9.1728394107787	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	18.345678821557	1 Cum.

4	R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	48.937935824952	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.13066428865262	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	6.166179913944	1Mtr.
5	Concrete (AR0307) :-Third floor - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	5.6130910756161	Cum
i)	BRM340 : Cement	3.23	18.13028417424	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.5258909840272	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	5.0517819680545	1 Cum.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	9.4238423100864	1 Cum	1154.65	10881.239523341

2	BRM340	61.892372196497	1 Qntl.	544.417	33695.2595941
3	BRM028	11.698730394806	1 Cum	1159.59	13565.730778513
4	BRM044	18.345678821557	1 Cum.	1713.94	31443.39275942
5	BRM104	0.13066428865262	1Cum.	58573.086	7653.4106163788
6	BRM092	6.166179913944	1Mtr.	229.106	1412.708815364
7	BRM056	5.0517819680545	1 Cum.	2115.31	10686.084914845
					Total: 109337.82700196