

ESTIMATION DPR							
State	Odisha	District	Kendujhar	Block	Telkoi	Gram Panchayat	Binjabahal

Work Code	OD/361/3455/119517/386327/00029860 (Construction Of C.C Road From Gouranga Majhi Ghara To Kaliakudar Ghata, Binjabahal)						
Project Category	Road						

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Telkoi	Proposal Date	16-12-2024
Date of Commencement	28-09-2025	Date of Completion	29-01-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	Saoumya Ranjan Tarei		

Administrative Approval Details

Approval No.	OD/361/3455/119517/386327/00029860/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/361/3455/119517/386327/00029860/TS
Fund Sanction No.	29781
Fund Sanction Amount (in Rs.)	450000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<p>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	7.38368488704	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	24.7639194208	Cum
i)	BRM029 : Sand for filling and road blinding	1	24.7639194208	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	30.3576200928	Cum
i)	BRM340 : Cement	2.29	69.518950012512	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	14.571657644544	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	29.143315289088	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	26.688017664	Cum
i)	BRM340 : Cement	3.23	86.20229705472	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	12.0096079488	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	24.0192158976	1 Cum.
5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	22.110914	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.05903614038	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	2.785975164	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	24.7639194208	1 Cum	591.41	14645.629584655
2	BRM340	155.72124706723	1 Qntl.	616.087	95937.83594191
3	BRM028	26.581265593344	1 Cum	536.31	14255.798550366
4	BRM044	29.143315289088	1 Cum.	1857.16	54123.799422283
5	BRM056	24.0192158976	1 Cum.	2231.91	53608.728154012
6	BRM104	0.05903614038	1Cum.	58620.646	3460.7366864223
7	BRM092	2.785975164	1Mtr.	276.666	770.78460472322
					Total: 236803.31294437