

ESTIMATION DPR							
State	Odisha	District	Gajapati	Block	Mohona	Gram Panchayat	Badasinghab a

Work Code	OD/353/3360/117492/413911/00030746 (Constrcution Of All Weather Road From Ruamba RD Road To Kharigumma)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Mohona	Proposal Date	-
Date of Commencement	01-11-2025	Date of Completion	02-01-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	Pradymna Kumar Nayak		

Administrative Approval Details

Approval No.	OD/353/3360/117492/413911/00030746/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/353/3360/117492/413911/00030746/TS
Fund Sanction No.	15598
Fund Sanction Amount (in Rs.)	170000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	11.62876	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	7.8793	Cum
i)	BRM029 : Sand for filling and road blinding	1	7.8793	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	11.62876	Cum
i)	BRM340 : Cement	2.29	26.6298604	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	5.5818048	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	11.1636096	1 Cum.

4	<p>R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	32.604	Sqm
i)	<p>BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)</p>	0.00267	0.08705268	1Cum.
ii)	<p>BRM092 : Non-sal bullahs 75mm. mean dia of any length.</p>	0.126	4.108104	1Mtr.
5	<p>Concrete (AR0307) :-Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	9.0155	Cum
i)	<p>BRM340 : Cement</p>	3.23	29.120065	1 Qntl.
ii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.45	4.056975	1 Cum
iii)	<p>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</p>	0.9	8.11395	1 Cum.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	7.8793	1 Cum	673.45	5306.314585
2	BRM340	55.7499254	1 Qntl.	789.677	44024.433840096
3	BRM028	9.6387798	1 Cum	678.39	6538.851828522
4	BRM044	11.1636096	1 Cum.	1401.46	15645.352310016
5	BRM104	0.08705268	1Cum.	58668.206	5107.2245630921
6	BRM092	4.108104	1Mtr.	324.226	1331.954127504
7	BRM056	8.11395	1 Cum.	1802.83	14628.0724785
					Total: 92582.20373273