

ESTIMATION DPR							
State	Odisha	District	Koraput	Block	Bandhugaon	Gram Panchayat	Neelabadi

Work Code	OD/363/3466/119713/428775/00035574 (Improvement of Road with Paver Block near Nilabadi GP Facility Centre)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Bandhugaon	Proposal Date	-
Date of Commencement	04-02-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	Pavor Block	Project Type	New Work
Name of Executant	Rosan Guria		

Administrative Approval Details

Approval No.	OD/363/3466/119713/428775/00035574/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/363/3466/119713/428775/00035574/TS
Fund Sanction No.	35917
Fund Sanction Amount (in Rs.)	350000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	33.5566	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	28.952	Cum
i)	BRM029 : Sand for filling and road blinding	1	28.952	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	14.455	Cum
i)	BRM340 : Cement	2.29	33.10195	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	6.9384	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	13.8768	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	5.971	Cum
i)	BRM340 : Cement	3.23	19.28633	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.68695	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	5.3739	1 Cum.

5	<p>miscellaneous(ARM28 7) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	254.1	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03	7.623	1 Cum
ii)	BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	254.1	1 Sqm

6	R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	85	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.22695	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	10.71	1Mtr.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	36.575	1 Cum	608.35	22250.40125
2	BRM340	52.38828	1 Qntl.	583.047	30544.82948916
3	BRM028	9.62535	1 Cum	872.67	8399.7541845
4	BRM044	13.8768	1 Cum.	1792.06	24868.058208
5	BRM056	5.3739	1 Cum.	2193.43	11787.273477
6	BRMM287	254.1	1 Sqm	608.4	154594.44
7	BRM104	0.22695	1Cum.	58953.566	13379.5118037
8	BRM092	10.71	1Mtr.	609.586	6528.66606
Total: 272352.93447236					