

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Rayagada	<b>Block</b>	Padmapur	<b>Gram Panchayat</b>	Naira

<b>Work Code</b>	OD/370/3555/121233/427010/00036624 (Improvement Of Chintalguda Tank)
<b>Project Category</b>	Water Body

<b>Financial Year</b>	2023-24	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Padmapur	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	18-11-2025	<b>Date of Completion</b>	20-12-2025
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance of Capital Assets
<b>Project Sub-Category</b>	Tank	<b>Project Type</b>	Renovation or Rejuvenation
<b>Name of Executant</b>	MANMOHAN SINGH		

### Administrative Approval Details

<b>Approval No.</b>	OD/370/3555/121233/427010/00036624/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/370/3555/121233/427010/00036624/TS
<b>Fund Sanction No.</b>	11826
<b>Fund Sanction Amount (in Rs.)</b>	119230

### MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>5.28525</b>	Cum

2	<b>Earth Work (AR0115)</b> :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	3.95	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	3.95	1 Cum
3	<b>Concrete (AR0303)</b> :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.68525	Cum
i)	<b>BRM340</b> : Cement	2.29	22.1792225	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	4.64892	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	9.29784	1 Cum.

4	<b>R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	2.7	Qntl
i)	<b>BRM162 : Binding Wire.</b>	0.8	2.16	1 Kg.
ii)	<b>BRM341 : Steel</b>	1.05	2.835	1 Qntl.
5	<b>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	4.9375	Cum
i)	<b>BRM340 : Cement</b>	3.23	15.948125	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	2.221875	1 Cum
iii)	<b>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve &amp; retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</b>	0.9	4.44375	1 Cum.

6	<b>R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</b>	-	12.5175	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.033421725	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	1.577205	1Mtr.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	3.95	1 Cum	478.15	1888.6925
2	<b>BRM340</b>	38.1273475	1 Qntl.	543.752	20731.82145782
3	<b>BRM028</b>	6.870795	1 Cum	483.09	3319.21235655
4	<b>BRM044</b>	9.29784	1 Cum.	1421.31	13215.1129704
5	<b>BRM162</b>	2.16	1 Kg.	90.1	194.616
6	<b>BRM341</b>	2.835	1 Qntl.	6626.072	18784.91412
7	<b>BRM056</b>	4.44375	1 Cum.	1867.93	8300.6139375
8	<b>BRM104</b>	0.033421725	1Cum.	58573.086	1957.6135726934
9	<b>BRM092</b>	1.577205	1Mtr.	229.106	361.34712873
<b>Total: 68753.944043693</b>					