

ESTIMATION DPR							
State	Odisha	District	Ganjam	Block	Chikiti	Gram Panchayat	Chandapur

Work Code	OD/354/3370/117690/412982/00038797 (Completion of Incomplete Dhoba Samaja Community Hall Baidyanalasan)						
Project Category	Building						

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Chikiti	Proposal Date	21-05-2025
Date of Commencement	01-12-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO ZILLA PARISHAD
Project Sub-Category	Community Centre	Project Type	Upgradation or Improvement
Name of Executant	SUCHISMITA MISHRA		

Administrative Approval Details

Approval No.	OD/354/3370/117690/412982/00038797/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3370/117690/412982/00038797/TS
Fund Sanction No.	6911
Fund Sanction Amount (in Rs.)	285722

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	7.799667882	Cum
i)	BRM340 : Cement	3.4733	27.090586454551	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.5098505469	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.80788043752	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	4.21182065628	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	34.471412171287	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.32391240747158	1Cum.

2	<p>Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	3.490187184	Cum
i)	BRM340 : Cement	2.29	7.99252865136	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	1.67528984832	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	3.35057969664	1 Cum.
3	<p>R.C.C. Work (AR0410d) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm</p>	-	16.72254	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	9.2372125714286	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.086797945714286	1Cum.

4	R.C.C. Work (AR0410e) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	11.77545525	Sqm
i)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	3.170314875	1Mtr.
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.062349525875	1Cum.
5	R.C.C. Work (AR0410a) :.Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	57.0287945493	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.622222222222222	35.48458327512	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.28641127929204	1Cum.

6	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	66.797257	Sqm
i)	BRM340 : Cement	0.0358	2.3913418006	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.001958855	1 Cum
7	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	8	Qntl
i)	BRM162 : Binding Wire.	0.8	6.4	1 Kg.
ii)	BRM341 : Steel	1.05	8.4	1 Qntl.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM340	37.474456906511	1 Qntl.	634.632	23782.489535493
2	BRM028	6.18709925022	1 Cum	407.34	2520.2530085846
3	BRM060	2.80788043752	1 Cum.	1944.18	5459.0249890176
4	BRM052	4.21182065628	1 Cum.	1918.7	8081.2202932044
5	BRM084	79.193208017836	1Mtr	250.166	19811.44807699
6	BRM104	0.7594711583529	1Cum.	58573.086	44484.569472724
7	BRM045	3.35057969664	1 Cum.	1323.77	4435.3968850211

8	BRM094	3.170314875	1Mtr.	240.106	761.21162337675
9	BRM162	6.4	1 Kg.	90.1	576.64
10	BRM341	8.4	1 Qntl.	6716.082	56415.0888
					Total: 166327.34268441