

ESTIMATION DPR							
State	Odisha	District	Sundargarh	Block	Rajgangpur	Gram Panchayat	Laing

Work Code	OD/373/3586/121737/384208/00039093 (CONSTRUCTION OF GUARD WALL AT KUMBHARPADA VILLAGE ROAD)
Project Category	Water Body

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Rajgangpur	Proposal Date	-
Date of Commencement	23-07-2025	Date of Completion	08-08-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	Guard Wall or Retaining Wall or Protection Wall	Project Type	New Work
Name of Executant	RUPAK KUMAT PATEL		

Administrative Approval Details

Approval No.	OD/373/3586/121737/384208/00039093/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/373/3586/121737/384208/00039093/TS
Fund Sanction No.	12442
Fund Sanction Amount (in Rs.)	400000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	44	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	4.4	Cum
i)	BRM029 : Sand for filling and road blinding	1	4.4	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.94	Cum
i)	BRM340 : Cement	2.29	13.6026	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	2.8512	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	5.7024	1 Cum.

4	Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	66	Sqm
i)	BRM340 : Cement	0.0372	2.4552	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.495	1 Cum
5	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	13.4448	Qntl
i)	BRM162 : Binding Wire.	0.8	10.75584	1 Kg.
ii)	BRM341 : Steel	1.05	14.11704	1 Qntl.

6	<p>R.C.C. Work (AR0404Aa) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	36.96	Cum
i)	BRM340 : Cement	3.4733	128.373168	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	16.632	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	13.3056	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	19.9584	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.1480248	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	6.98544	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	4.4	1 Cum	413.05	1817.42
2	BRM340	144.430968	1 Qntl.	573.137	82778.731706616
3	BRM028	19.9782	1 Cum	417.99	8350.687818
4	BRM044	5.7024	1 Cum.	1271.26	7249.233024
5	BRM162	10.75584	1 Kg.	90.1	969.101184
6	BRM341	14.11704	1 Qntl.	6641.597	93759.69051288
7	BRM060	13.3056	1 Cum.	1666.01	22167.262656
8	BRM052	19.9584	1 Cum.	1658.3	33097.01472
9	BRM104	0.1480248	1Cum.	58791.862	8702.6536141776
10	BRM092	6.98544	1Mtr.	447.882	3128.65283808
Total:					262020.44807375