

ESTIMATION DPR							
State	Odisha	District	Sundargarh	Block	Tangarpali	Gram Panchayat	Mahulpali

Work Code	OD/373/3589/121773/383899/00039294 (Renovation of Bandhapali Junabandh at Bandhapali)
Project Category	Water Body

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Tangarpali	Proposal Date	-
Date of Commencement	20-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Tank	Project Type	Renovation or Rejuvenation
Name of Executant	PANCHAMI DHURUA		

Administrative Approval Details

Approval No.	OD/373/3589/121773/383899/00039294/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/373/3589/121773/383899/00039294/TS
Fund Sanction No.	26956
Fund Sanction Amount (in Rs.)	250000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	46.725	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	19.1625	Cum
i)	BRM029 : Sand for filling and road blinding	1	19.1625	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.4	Cum
i)	BRM340 : Cement	2.29	19.236	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.032	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	8.064	1 Cum.

4	<p>R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	84	Sqm
i)	<p>BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)</p>	0.00267	0.22428	1Cum.
ii)	<p>BRM092 : Non-sal bullahs 75mm. mean dia of any length.</p>	0.126	10.584	1Mtr.
5	<p>Concrete (AR0307) :Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	0.7875	Cum
i)	<p>BRM340 : Cement</p>	3.23	2.543625	1 Qntl.
ii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.45	0.354375	1 Cum
iii)	<p>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</p>	0.9	0.70875	1 Cum.

6	miscellaneous(ARM286) :.Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	255.5	Sqm
i)	BRM029 : Sand for filling and road blinding	0.05	12.775	1 Cum
ii)	BRMM286 : Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	255.5	1 Sqm

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	31.9375	1 Cum	478.15	15270.915625
2	BRM340	21.779625	1 Qntl.	555.297	12094.160423625
3	BRM028	4.386375	1 Cum	483.09	2119.01389875
4	BRM044	8.064	1 Cum.	1375.42	11091.38688
5	BRM104	0.22428	1Cum.	58620.646	13147.43848488
6	BRM092	10.584	1Mtr.	276.666	2928.232944
7	BRM056	0.70875	1 Cum.	1776.79	1259.2999125
8	BRMM286	255.5	1 Sqm	485.28	123989.04

