

ESTIMATION DPR							
State	Odisha	District	Kandhamal	Block	K.Nuagan	Gram Panchayat	Chanchedi

Work Code	OD/359/3426/118925/416199/00039742 (IMP OF TAPOBANA PAISAMUNDA TANK)
Project Category	Water Body

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, K.Nuagan	Proposal Date	06-02-2023
Date of Commencement	13-09-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO ZILLA PARISHAD
Project Sub-Category	Tank	Project Type	Renovation or Rejuvenation
Name of Executant	SAROJ KUMAR PRADHAN		

Administrative Approval Details

Approval No.	OD/359/3426/118925/416199/00039742/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/359/3426/118925/416199/00039742/TS
Fund Sanction No.	4506
Fund Sanction Amount (in Rs.)	200000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p>Special items for irrigation works(AR0216) .Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum within an initial lead of 1km from the place of excavation. - Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete. Per 1 cum.</p>	-	2883.742945	Cum
i)	BRMMR0065 : Add for trimming of slope and bed manually.	1	2883.742945	L.S.
ii)	BRMMR0102 : Cost of mechanical excavation per cum without supervision charge for item AR0216	1	2883.742945	Cum
iii)	BRMMR0104 : Cost of transportation of loose earth within the initial lead of 1 km, excluding supervision charges - AR0216	1	2883.742945	Cum

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRMMR0065	2883.742945	L.S.	1	2883.742945
2	BRMMR0102	2883.742945	Cum	25.01	72122.41105445
3	BRMMR0104	2883.742945	Cum	40.49	116762.75184305

Total: 191768.9058425