

ESTIMATION DPR							
State	Odisha	District	Malkangiri	Block	Kalimela	Gram Panchayat	Bhejangiwad a

Work Code	OD/364/3480/119929/431055/00040643 (Construction of culvert on village road of MPV-71)
Project Category	CD Work

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Kalimela	Proposal Date	-
Date of Commencement	15-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	Slab Culvert	Project Type	New Work
Name of Executant	Susanta Sahu AE		

Administrative Approval Details

Approval No.	OD/364/3480/119929/431055/00040643/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/364/3480/119929/431055/00040643/TS
Fund Sanction No.	28788
Fund Sanction Amount (in Rs.)	300000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	27	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	4.05	Cum
i)	BRM029 : Sand for filling and road blinding	1	4.05	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	40.9585	Cum
i)	BRM340 : Cement	2.29	93.794965	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	19.66008	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	39.32016	1 Cum.

4	<p>R.C.C. Work (AR0404Aa) ∴ Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	4.3875	Cum
i)	BRM340 : Cement	3.4733	15.23910375	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.974375	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.5795	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.36925	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.0175719375	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	0.8292375	1Mtr.

5	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	3.4589	Qntl
i)	BRM162 : Binding Wire.	0.8	2.76712	1 Kg.
ii)	BRM341 : Steel	1.05	3.631845	1 Qntl.
6	Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	21	Sqm
i)	BRM340 : Cement	0.0372	0.7812	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.1575	1 Cum

7	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	1.05	Cum
i)	BRM340 : Cement	3.23	3.3915	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.4725	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	0.945	1 Cum.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	4.05	1 Cum	478.15	1936.5075
2	BRM340	113.20676875	1 Qntl.	578.733	65516.492898994
3	BRM028	22.264455	1 Cum	483.09	10755.73556595
4	BRM044	39.32016	1 Cum.	1531.66	60225.1162656
5	BRM060	1.5795	1 Cum.	1955.08	3088.04886
6	BRM052	2.36925	1 Cum.	1918.7	4545.879975
7	BRM104	0.0175719375	1Cum.	58582.598	1029.4097506436
8	BRM092	0.8292375	1Mtr.	238.618	197.870993775
9	BRM162	2.76712	1 Kg.	90.1	249.317512
10	BRM341	3.631845	1 Qntl.	6214.317	22569.436124865
11	BRM056	0.945	1 Cum.	1933.03	1826.71335

Total: 171940.52879683