

ESTIMATION DPR							
State	Odisha	District	Sambalpur	Block	Bamra	Gram Panchayat	Pindapathar

Work Code	OD/371/3558/121288/381321/00044351 (Preservation and Development of Dheto Pada Kata , Parmanpur)
Project Category	Water Body

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Bamra	Proposal Date	15-04-2023
Date of Commencement	04-10-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Preservation and Development of Water Bodies
Project Sub-Category	Inlet or Outlet or Surplus Escape	Project Type	Renovation or Rejuvenation
Name of Executant	manoranjanpradhanbamra		

Administrative Approval Details

Approval No.	OD/371/3558/121288/381321/00044351/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/371/3558/121288/381321/00044351/TS
Fund Sanction No.	12441
Fund Sanction Amount (in Rs.)	663375

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	34.971248	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	36.387088	Cum
i)	BRM029 : Sand for filling and road blinding	1	36.387088	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	53.85289024	Cum
i)	BRM340 : Cement	2.29	123.3231186496	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	25.8493873152	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	51.6987746304	1 Cum.

4	<p>R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	108.9566384	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.290914224528	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	13.7285364384	1Mtr.
5	<p>Concrete (AR0307) :-Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	2.12376	Cum
i)	BRM340 : Cement	3.23	6.8597448	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.955692	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1.911384	1 Cum.

6	<p>Special items for irrigation works(AR0216) .Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum within an initial lead of 1km from the place of excavation. - Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete. Per 1 cum.</p>	-		3709.5008	Cum
i)	BRMMR0065 : Add for trimming of slope and bed manually.	1		3709.5008	L.S.
ii)	BRMMR0102 : Cost of mechanical excavation per cum without supervision charge for item AR0216	1		3709.5008	Cum
iii)	BRMMR0104 : ost of transportation of loose earth within the initial lead of 1 km, excluding supervision charges - AR0216	1		3709.5008	Cum

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	36.387088	1 Cum	541.31	19696.69460528
2	BRM340	130.1828634496	1 Qntl.	568.732	74039.160295418
3	BRM028	26.8050793152	1 Cum	548.19	14694.276429799
4	BRM044	51.6987746304	1 Cum.	1903.91	98429.814006565
5	BRM104	0.290914224528	1Cum.	58763.326	17095.087413976
6	BRM092	13.7285364384	1Mtr.	419.346	5757.0068412973

7	BRM056	1.911384	1 Cum.	2350.53	4492.76543352
8	BRMMR0065	3709.5008	L.S.	1	3709.5008
9	BRMMR0102	3709.5008	Cum	25.01	92774.615008
10	BRMMR0104	3709.5008	Cum	40.49	150197.687392
					Total: 480886.60822586