

ESTIMATION DPR							
State	Odisha	District	Kendrapara	Block	Garadapur	Gram Panchayat	Bangalpur

Work Code	OD/360/3436/119091/396706/00045026 (Const. Of Road With Pavour Block From Ghoda Danad Nira Nayak House To Barik Sahi Road, Village Nuasasan)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Garadapur	Proposal Date	-
Date of Commencement	23-10-2025	Date of Completion	06-01-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	Repair and Maintenance
Name of Executant	PRADIP SAMANTRAY JE		

Administrative Approval Details

Approval No.	OD/360/3436/119091/396706/00045026/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/360/3436/119091/396706/00045026/TS
Fund Sanction No.	31142
Fund Sanction Amount (in Rs.)	133422

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	4.23225	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.56175	Cum
i)	BRM029 : Sand for filling and road blinding	1	9.56175	1 Cum
3	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	5.643	Cum
i)	BRM340 : Cement	3.23	18.22689	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.53935	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	5.0787	1 Cum.

4	<p>miscellaneous(ARM287) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	108.68	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03	3.2604	1 Cum
ii)	BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	108.68	1 Sqm

5	R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	50.16	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.1339272	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	6.32016	1Mtr.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	12.82215	1 Cum	340.19	4361.9672085
2	BRM340	18.22689	1 Qntl.	605.327	11033.22864303
3	BRM028	2.53935	1 Cum	347.82	883.236717
4	BRM056	5.0787	1 Cum.	2654.13	13479.530031
5	BRMM287	108.68	1 Sqm	608.4	66120.912
6	BRM104	0.1339272	1Cum.	58573.086	7844.5294033392
7	BRM092	6.32016	1Mtr.	229.106	1447.98657696
Total: 105171.39057983					