

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Mayurbhanj	<b>Block</b>	Udala	<b>Gram Panchayat</b>	Kundabai

<b>Work Code</b>	OD/365/3512/120414/390995/00049072 (Repair and maintenance of Kundabai Hata)
<b>Project Category</b>	Other Infrastructure

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Udala	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	17-11-2025	<b>Date of Completion</b>	12-01-2026
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance of Capital Assets
<b>Project Sub-Category</b>	Rural Haat	<b>Project Type</b>	Repair and Maintenance
<b>Name of Executant</b>	UGRASEN MALLIK		

### Administrative Approval Details

<b>Approval No.</b>	OD/365/3512/120414/390995/00049072/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/365/3512/120414/390995/00049072/TS
<b>Fund Sanction No.</b>	26956
<b>Fund Sanction Amount (in Rs.)</b>	240000

### MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	14.4982016	Cum

2	<b>Earth Work (AR0115)</b> :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>20.954432</b>	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	20.954432	1 Cum
3	<b>Plastering (AR1027)</b> :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	<b>81.197222</b>	Sqm
i)	<b>BRM340</b> : Cement	0.0372	3.0205366584	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.0075	0.608979165	1 Cum
4	<b>R.C.C. Work (AR0410c)</b> :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	<b>53.512128</b>	Sqm

i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.14287738176	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	6.742528128	1Mtr.
5	<b>Concrete (AR0303a)</b> :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>23.460610384</b>	Cum
i)	<b>BRM340</b> : Cement	2.29	53.72479777936	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	11.26109298432	1 Cum
iii)	<b>BRM045</b> : Granite Stone broken metal 40mm. size (Hand broken)	0.96	22.52218596864	1 Cum.
6	<b>Concrete (AR0307)</b> :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	<b>3.89356</b>	Cum
i)	<b>BRM340</b> : Cement	3.23	12.5761988	1 Qntl.

ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1.752102	1 Cum
iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	3.504204	1 Cum.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	20.954432	1 Cum	792.14	16598.84376448
2	<b>BRM340</b>	69.32153323776	1 Qntl.	650.622	45102.114598218
3	<b>BRM028</b>	13.62217414932	1 Cum	798.56	10878.123388681
4	<b>BRM104</b>	0.14287738176	1Cum.	58715.766	8389.1549141128
5	<b>BRM092</b>	6.742528128	1Mtr.	371.786	2506.7775625966
6	<b>BRM045</b>	22.52218596864	1 Cum.	1519.07	34212.777039382
7	<b>BRM056</b>	3.504204	1 Cum.	2128.33	7458.10249932
<b>Total:</b>					<b>125145.89376679</b>