

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Thakurmunda	Gram Panchayat	Digdhar

Work Code	OD/365/3510/120385/389065/00049440 (Construction of C.C.Road from Noto house to Sailesh house Khuntaposi, Digdhar)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Thakurmunda	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	OD/365/3510/120385/389065/00049440/TS
Fund Sanction No.	34188
Fund Sanction Amount (in Rs.)	300000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	18.25125	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.13175	Cum
i)	BRM029 : Sand for filling and road blinding	1	16.13175	1 Cum
3	Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	19.311	Cum
i)	BRM340 : Cement	2.29	44.22219	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	9.26928	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	18.53856	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	17.1915	Cum
i)	BRM340 : Cement	3.23	55.528545	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	7.736175	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	15.47235	1 Cum.
5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	37.68	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.1006056	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	4.74768	1Mtr.

6	Earth Work (AR0122Bi) :.Earthwork in ordinary soil within 5 Km. mechanical carriages and spreading in filling area/road berm within initial lead and lift - Earthwork in ordinary soil within 5 Km. mechanical carriages and spreading in filling area/road berm within initial lead and lift including dressing and leveling the bed, etc. as per direction of Engineer-in-Charge.	-	18.84	Cum
i)	BRMM402 : Loading into trucks and unloading from trucks within 50 Meter lead (2/3 of rate is consider for loading).	-0.6666	-12.558744	1 Cum
ii)	BRMM401 : Conveyance of material by 10 ton trucks within 5 KM including loading and unloading	1	18.84	1 Cum

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	16.13175	1 Cum	531.74	8577.896745
2	BRM340	99.750735	1 Qntl.	632.787	63120.968348445
3	BRM028	17.005455	1 Cum	1110.91	18891.53001405
4	BRM045	18.53856	1 Cum.	1709.21	31686.2921376
5	BRM056	15.47235	1 Cum.	2340.31	36210.0954285
6	BRM104	0.1006056	1Cum.	58620.646	5897.5652632176
7	BRM092	4.74768	1Mtr.	276.666	1313.52163488
8	BRMM402	-12.558744	1 Cum	175.38	-2202.55252272
9	BRMM401	18.84	1 Cum	276.01	5200.0284
Total: 168695.34544897					